**Office of the Illinois State Fire Marshal**
**Division of Petroleum and Chemical Safety**
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

**FOR OFFICE USE ONLY**
Facility #: 2048086
Permit #: 01329-2026INS
Request Rec'd: 10/18/2026
Approval Date: 10/27/2026 DS
Permit Expires: 04/27/2027

# Permit for INSTALLATION of Regulated Underground Storage Tanks and Piping

Permission is hereby granted to install the underground storage tank(s) and associated piping identified below. All installation activities must be conducted in accordance with all applicable sections of 41 Ill. Adm. Code Parts 174, 175, and 176. The permitted contractor must schedule specific dates and times for all required activities through their contractor portal account. Both the electronic testing forms and the Notification for Underground Storage Tank form must be submitted before the final inspection can be scheduled.

**THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

| **OWNER OF TANKS**<br>- Corporation, partnership, or other business entity: | **FACILITY**<br>- name and address where tanks are located: |
|---|---|
| Schiller Park Mart LLC<br>4802 N River Rd<br>Schiller Park, IL 60176<br><br>Contact: Schiller Park Mart LLC 630/456-6313 | Schiller Park Mart LLC<br>4802 N River rd<br>Schiller Park, IL 60176<br>Cook County<br><br>Contact: Jaimon Lukose 630/356-6313 |

**Tanks on the Permit**

| Tank # | Product | Capacity | Tank Status | Regulated Status |
|---|---|---|---|---|
| 1 | Gasoline - Regular | 15,000 | Tank Not Installed | Federal |
| 2 | Gasoline - Premium | 5,000 | Tank Not Installed | Federal |
| 3 | Diesel Fuel | 5,000 | Tank Not Installed | Federal |
| 4 | E85 | 5,000 | Tank Not Installed | Federal |

**Tank 1 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Franklin Fueling Systems EVO One | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L Vent | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech XP 1500 | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Fiberglass Double Wall XERXES | New |

**Tank 2 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Franklin Fueling Systems EVO One | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L Vent | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech XP 1500 | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Fiberglass Double Wall XERXES | New |

**Tank 3 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Franklin Fueling Systems EVO One | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L Vent | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech XP 1500 | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Fiberglass Double Wall XERXES | New |

**Tank 4 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Corrosion Protection - Piping | Flexible Non-Corrosive | New |
| Corrosion Protection - Tank | Fiberglass Non-Corrosive | New |
| Leak Detection - Piping | Electronic Pressurized Line Leak Detection | New |
| Leak Detection - Tank | Automatic Tank Gauging Franklin Fueling Systems EVO One | New |
| Leak Detection - Tank | Non-Discriminating Interstitial Monitoring Sensors | New |
| Overfill Prevention Device | Overfill Drop Tube Valve | New |
| Piping | Fiberglass Single Wall Piping Ameron 4000 L Vent | New |
| Piping | Flexible Double Wall A.P.T. Poly Tech XP 1500 | New |
| Piping | Single Wall STP/Tanktop Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |
| Spill Containment Device | Double Wall Spill Bucket | New |
| Tank | Fiberglass Double Wall XERXES | New |

**Dispensers on the Permit**

| Dispenser | Action |
|---|---|
| 1/2 | New |
| 3/4 | New |
| 5/6 | New |
| 7/8 | New |
| 9/10 | New |

**Dispenser 1/2 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

**Dispenser 3/4 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

**Dispenser 5/6 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

**Dispenser 7/8 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

**Dispenser 9/10 Equipment**

| Equipment Type | Permit Equipment | Action |
|---|---|---|
| Dispenser | Single Wall UDC Sump | New |
| ↳ Leak Detection - Piping | Sump Sensor with positive shutdown | New |

**General Requirements**
USTs shall be installed to safeguard against movement by anchoring in accordance with manufacturer's instructions.
There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**Summary of Work**
This is a new Ground up gas station

Thanks
Innovative Constructions

**Special Contingencies**
**NOTES: Dispensers must be a full 10' from all building and property lines. Vents must meet section 175.440 of our rules.**

| PERSON, FIRM OR COMPANY PERFORMING WORK: | |
|---|---|
| Innovative Constructions Technology LLC<br>245 W Roosevelt Rd Building 4, Unit 28<br>West Chicago, IL 60185 | Contact Person: Raju penumatsa<br>Phone: 630/747-3404<br>Email: iconstructions81@gmail.com<br>Contractor License # IL002453 Exp. 2/7/2028 |

Sincerely,



Daniel Starks