Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
217/785-1020
www.sfm.illinois.gov
SFM.DPCS@illinois.gov

FOR OFFICE USE ONLY
Facility #: 2017783
Permit #: 01350-2026REM
Request Rec'd: 11/03/2026
Approval Date: 11/04/2026 DS
Permit Expires: 05/04/2027

Permit for REMOVAL of Regulated Underground Storage Tanks and Piping

Permission is hereby granted to remove the underground storage tank(s) and/or associated piping identified below. All removal activities must be conducted in accordance with all applicable sections of 41 Ill. Adm. Code Parts 174, 175, and 176. The permitted contractor must schedule a date certain for the UST removal through their contractor portal account. If the Storage Tank Safety Specialist (STSS) observes evidence of a release, the owner, operator, or designated representative must notify the Illinois Emergency Management Agency at (800)782-7860. This is to be done at the site immediately following the field determination and the incident number shall be given to the STSS prior to his/her leaving the site. All removals require a site assessment and must be performed in accordance with 35 Ill. Adm. Code 734.210(h)(1) and (2). Samples shall be taken in native soil with the excavation for the removal still open and prior to backfill and with the STSS still on site.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

OWNER OF TANKS - Corporation, partnership, or other business entity:	**FACILITY** - name and address where tanks are located:
Aurora Packing Company, Inc. 125 Grant Street North Aurora, IL 60542 Kane County Contact: Don Zeko 331/454-1250	Aurora Packing Company, Inc. 125 Grant Street North Aurora, IL 60542 Kane County 15-03-301-020 Contact: Don Zeko 630/897-0551

Tanks on the Permit

Tank #	Capacity	Product	Last Used Date
4	2,000	Diesel Fuel	07/31/2026

Summary of Work
Generators that utilized the UST for Diesel fuel will be removed from the area. The concrete slab will be removed over the tank. The soils above and around the top of the tank will be removed using a hydraulic excavator. The remaining liquids inside the tank will be pumped and recycled. The atmosphere inside the tank will be rendered inert using a venting appartus connected to a 125 cfm compressor. Once the tank is determined to be in a safe condition, the hydraulic excavator will be used to remove the tank from the ground. the ends of the tank will be opened to allow access by personnel to clean the interior. Once cleaned, the tank will be removed from the site and hauled to be recycled.

Special Contingencies
Removal of tank and all associated piping

The owner must notify this Office when completion of tank removal has occurred, on the Notification for Underground Storage Tank Form. This form can be obtained at www.sfm.illinois.gov or by calling (217)785-1020. After removal is completed, the owner/operator shall perform a site assessment by measuring for the presence of a release where contamination is most likely to be present at the UST site. This is in accordance with the Illinois Administrative Code 176.360 (a) regulations and 40 CFR Part 280.72 (a) Federal Register Requirement.

PERSON, FIRM OR COMPANY PERFORMING WORK:	
Alessio & Sons Company 377 E Butterfield Rd Ste 270 Lombard, IL 60148	Contact Person: Vera Erickson Phone: 773/269-7339 Email: pclarke@alessiocompanies.com Contractor License # IL764 Exp. 10/28/2028

Sincerely,



Daniel Starks