



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)785-1020

FOR OFFICE USE ONLY

Facility # 2-031993
Permit # 00897-2013INS
Request Rec'd 09/05/2013
Amended Date
Approval Date 9/5/2013 DS
Permit Expires 3/5/2014

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Speedway, LLC P.O. Box 1500 Springfield, OH 45501-1500 Contact: Anthony Thomas (937) 863-7633	(2) FACILITY - name and address where tanks are located: Speedway #7382 21 West 400 North Avenue Lombard, Du Page Co., IL Contact: Sanir B Shah (630) 916-1944
---	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed:** (TK # 12, 13, 14) - 20,000 gallons, (TK # 15) - 12,000 gallons, (TK # 16) - 8,000 gallons, (TK # 17) - 4,000 gallons, (TK # 18) - 10,000 gallons
- (b) Type of tanks:** (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Fiberglass Double Wall Containment Solutions
- (c) Type of piping:** (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Fiberglass Single Wall Vent Piping Ameron , (TK # 12, 13, 14, 15, 16, 17) - (Installing) Flexible Double Wall Franklin Fueling Systems UPP product piping **with a siphon bar between tanks 1 & 2, and also manifold piping between tanks 1 & 2 just outside of the submersible pump area**, (TK # 18) - (Installing) Flexible Double Wall OmegaFlex DoubleTrac
- (d) Product to be stored in each tank:** (TK # 12, 13, 15) - Diesel Fuel, (TK # 14, 16) - Gasoline, (TK # 17) - E-85, **(TK # 18) - Diesel Exhaust Fluid (Non-Regulated)**
- (e) Type of leak detection being used:**
 - Tank:** (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Automatic Tank Gauging Veeder Root TLS 450 with CSLD, printer and MAG Plus probes , (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Interstitial Monitoring Veeder Root TLS 450
 - Piping:** (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Electronic Pressurized Line Leak Detection Veeder Root TLS 450 , (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 450 in all submersible and dispenser sumps
- (f) Corrosion Protection being used:**
 - Tank:** (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Fiberglass Non-Corrosive
 - Piping:** (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Flexible Non-Corrosive
- (g) Spill containment devices, piping and dispenser containment devices:** (TK # 12, 13, 14, 15, 16, 17, 18) - (Installing) Manhole Pre-manufactured Emco Wheaton A1004
- (h) Overfill prevention devices:** (TK # 12, 13, 14, 15, 16, 18) - (Installing) Overfill Drop Tube Valve OPW 71SO , (TK # 17) - (Installing) Overfill Drop Tube Valve OPW 61SO

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.**

- (5) GENERAL REQUIREMENTS:** There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

- (6) SPECIAL CONTINGENCIES:** The underground storage tank system for tank #17 must be compatible with E-85, as indicated in section 175.415 of Title 41 of the Illinois Administrative Code. Tanks being siphoned together (tanks 1 & 2) must be within 6' elevation of each other.


(7) PERSON, FIRM OR COMPANY PERFORMING WORK:

DRW Services, Inc.
600 East Joe Orr Road
Chicago Heights, IL 60411

Contact Person: Raymond Kirchner
Phone: (708) 758-3222 Ext. 12

Contractor Registration # IL-194 Exp. 03/10/2014

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist -
Fire Department -
Division File
(Rev. - 9/10)