

OFFICE OF THE ILLINOIS STATE FIRE MARSHAL Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, Illinois 62703-4259 (217)785-1020 Facility # 2-024618 Permit # 00865-2013UPG Request Rec'd 08/27/2013 Amended Date

FOR OFFICE USE ONLY

Approval Date 9/12/2013 JC Permit Expires 3/12/2014

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for underground piping upgrade, leak detection, spill and overfill prevention of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety.

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity:	(2) <u>FACILITY</u> - name and address where tanks are located:
Speedway, LLC P.O. Box 1500 Springfield, OH 45501-1500	Speedway SuperAmerica 4251 1021 North Rand Road Prospect Heights, Cook Co., IL
Contact: Anthony Thomas (937) 863-7633	Contact: Dipak Parikh (847) 398-2711

(3) <u>UPGRADE OR REPAIR OF TANKS:</u>

- (a) Number and size of tanks being upgraded or repaired: (TK # 4) 8,000 gallons
- (b) Type of tanks:
- (c) Type of piping: (TK # 4) (Installing) Dispenser Sumps containment FRP 3 dispenser sumps will be installed under the existing north gas / diesel dispensers nearest to the building. The middle diesel dispensers are being eliminated, (TK # 4) (Installing) Transition Sumps FRP fiberglass next to where the eliminated middle row of diesel dispensers were, (TK # 4) (Installing) partial Fiberglass Double Wall Ameron Dualoy 3000/LCX from the three new transition sumps to the three existing north row dispensers to allow for the north row of dispensers to become 3+1 gas / diesel dispensers. Inspector NOTE: according to the facility file, the majority of the piping at this site is single wall steel and the corrosion protection for the tanks and piping is impressed current.
- (d) Product to be stored in each tank: (TK # 4) Diesel Fuel
- (e) Type of leak detection being used:

Tank:

Piping: (TK # 4) - (Installing) Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350 at the three new transition sumps and at the three north row gas / diesel dispenser sumps only.

(f) Corrosion Protection being used:

Tank:

Piping: (TK # 4) - (Installing) partial Fiberglass Non-Corrosive. See above inspector note in section (c).

- (g) Spill containment devices, piping, and dispenser containment devices:
- (h) Overfill prevention devices:
- (i) Manway accessible at grade:
- (4) The owner must notify this Office when completion of tank upgrade/repair has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for underground piping upgrade, leak detection, spill and overfill prevention to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.
- (5) **SPECIAL CONTINGENCIES**:

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

RJS-1 Construction, Inc. 3843 Long Point Blacktop Road Ancona, IL 61311 Contact Person: Randy Finck Phone: (815) 712-3245

Contractor Registration # IL-002356 Exp. 04/09/2014

Sincerely,

Jim Coffey

James of Coffey

Fire Department - Division File (Rev. - 9/10)