



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)785-1020

Amended

FOR OFFICE USE ONLY

Facility # 4-045658
Permit # 00671-2014INS
Request Rec'd 07/21/2014
Amended Date 09/15/2014
Approval Date 7/21/2014 JC
Permit Expires 1/21/2015

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Niemann Foods, Inc. 1501 North 12th Street, P. O. Box C-847 Quincy, IL 62306-0847 Contact: Andrew Hermsmeir (573) 393-2039	(2) FACILITY - name and address where tanks are located: County Market 1175 W Grand Ave Decatur, Macon Co., IL Contact:
--	--

(3) INSTALLATION OF TANKS:

- (a) **Number and size of tanks being installed:** (TK # 1) - 20,000 gallons, and one compartment tank consisting of the following two tanks: (TK # 2) - 10,000 gallons, (TK # 3) - 6,000 gallons
- (b) **Type of tanks:** (TK # 1, 2, 3) - (Installing) Fiberglass Double Wall XERXES
- (c) **Type of piping:** (TK # 1, 2, 3) - (Installing) Dispenser Sumps containment FRP, (TK # 1, 2, 3) - (Installing) Submersible Sumps containment FRP, (TK # 1, 2, 3) - (Installing) Fiberglass Double Wall Ameron Dualoy 3000/LCX
- (d) **Product to be stored in each tank:** (TK # 1, 3) - Gasoline, (TK # 2) - Diesel Fuel
- (e) **Type of leak detection being used:**
Tank: (TK # 1, 2, 3) - (Installing) Interstitial Monitoring Veeder Root TLS 450 , (TK # 1, 2, 3) - (Installing) Automatic Tank Gauging Veeder Root TLS 450 with CSLD
Piping: (TK # 1, 2, 3) - (Installing) Electronic Pressurized Line Leak Detection Veeder Root TLS 450 , (TK # 1, 2, 3) - (Installing) Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 450 at all submersible sumps and at all dispenser sumps.
- (f) **Corrosion Protection being used:**
Tank: (TK # 1, 2, 3) - (Installing) Fiberglass Non-Corrosive
Piping: (TK # 1, 2, 3) - (Installing) Fiberglass Non-Corrosive
- (g) **Spill containment devices, piping and dispenser containment devices:** (TK # 1, 2, 3) - (Installing) Manhole Pre-manufactured OPW 1C-3101DEV 5 gallon
- (h) **Overfill prevention devices:** (TK # 1, 2, 3) - (Installing) Overfill Drop Tube Valve OPW 61SOR
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.
- (5) **GENERAL REQUIREMENTS:** There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.
- (6) **SPECIAL CONTINGENCIES:** **Original permit was issued with an incorrect facility number due to the county being entered wrong. Amendment request is to show the amended location of the remote fills. They will be approximately 3' longer than what was originally permitted. Section 175.445(e) and (f) will still apply to the remote fills. Also, the overfill device will be OPW 61SOR drop tubes as opposed to the OPW 71SO-410C.**

(7) PERSON, FIRM OR COMPANY PERFORMING WORK:

Neumayer Equipment Company, Inc.
5060 Arsenal Street
Saint Louis, MO 63139

Contact Person: Justin Burkemper
Phone: (314) 772-4501

Contractor Registration # IL-1502 Exp. 03/26/2016

Sincerely,

A handwritten signature in cursive script, reading "Jim Coffey", is written over a horizontal line.

Jim Coffey

cc: Storage Tank Safety Specialist -
Fire Department -
Division File
(Rev. - 9/10)