



**OFFICE OF THE ILLINOIS STATE FIRE MARSHAL**  
**Division of Petroleum and Chemical Safety**  
 1035 Stevenson Drive  
 Springfield, Illinois 62703-4259  
 (217)785-1020

<u>FOR OFFICE USE ONLY</u>
Facility # 2-010868
Permit # 00876-2014INS
Request Rec'd 09/15/2014
Amended Date
Approval Date 9/15/2014 DS
Permit Expires 3/16/2015

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p><b>(1) OWNER OF TANKS</b> - Corporation, partnership, or other business entity:          Village of Lombard          255 E. Wilson Avenue          Lombard, IL 60148          Contact: John Mannio (630) 620-5755</p>	<p><b>(2) FACILITY</b> - name and address where tanks are located:          Village of Lombard          255 E. Wilson Ave.          Lombard, Du Page Co., IL          Contact: Angela Podesto (630) 620-5709</p>
--	--

**(3) INSTALLATION OF TANKS:**

- (a) Number and size of tanks being installed:* (TK # 6, 7) - 12,000 gallons
- (b) Type of tanks:* (TK # 6, 7) - (Installing) Fiberglass Double Wall XERXES
- (c) Type of piping:* (TK # 6, 7) - (Installing) Fiberglass Single Wall Piping Ameron Vent piping , (TK # 6, 7) - (Installing) Submersible Sumps containment FRP, (TK # 6, 7) - (Installing) Fiberglass Double Wall Ameron Dualoy 3000/LCX product piping from new tanks to new dispensers , (TK # 6, 7) - (Installing) Dispenser Sumps containment FRP
- (d) Product to be stored in each tank:* (TK # 6) - Gasoline, (TK # 7) - Diesel Fuel
- (e) Type of leak detection being used:*  
  - Tank:** (TK # 6, 7) - (Installing) Automatic Tank Gauging Veeder Root TLS 350 , (TK # 6, 7) - (Installing) Interstitial Monitoring Veeder Root TLS 350
  - Piping:** (TK # 6, 7) - (Installing) European with No Test Req Suction
- (f) Corrosion Protection being used:*  
  - Tank:** (TK # 6, 7) - (Installing) Fiberglass Non-Corrosive
  - Piping:** (TK # 6, 7) - (Installing) Fiberglass Non-Corrosive
- (g) Spill containment devices, piping and dispenser containment devices:* (TK # 6, 7) - (Installing) Manhole Pre-manufactured OPW 1-2100
- (h) Overfill prevention devices:* (TK # 6) - (Installing) Overfill Drop Tube Valve OPW 71SO , (TK # 7) - (Installing) Overfill Drop Tube Valve OPW 61SOC


**(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at [www.sfm.illinois.gov](http://www.sfm.illinois.gov) or by calling (217)785-1020.**

**(5) GENERAL REQUIREMENTS:** There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**(6) SPECIAL CONTINGENCIES:**

<p><b>(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u></b>          Accurate Tank Construction          204 Poplar Place          North Aurora, IL 60542</p>	<p>Contact Person: Jason Reed          Phone: (630) 375-6121          Contractor Registration # IL-002360 Exp. 08/28/2016</p>
---	---

Sincerely,



---

Daniel Starks

cc: Storage Tank Safety Specialist -  
Fire Department -  
Division File  
(Rev. - 9/10)