

Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 (217)785-1020

FOR OFFICE USE ONLY

Facility # 2045890 Permit # 00490-2015INS Request Rec'd 05/28/2015 Amended Date Approval Date 6/3/2015 DS Permit Expires 12/3/2015

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety.

THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business

ntity:

Meijer Great Lakes Limited Partnership 2929 Walker Avenue, NW Grand Rapids, MI 495449428

Contact: Brian Honsfud (616) 791-5778

(2) FACILITY - name and address where tanks are located:

Meijer Cas #280 3740 Vollmer Rd Flossmoor, IL 60422

Contact: (616) 791-5778

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK#6) 20,000, (TK#7, 8, 9) 8,000, (TK#10) 6,000
- (b) Type of tank(s): (TK#6, 7, 8, 9, 10) Tank Fiberglass Brine Filled Double Wall XERXES
- (c) Type of piping: (TK # 6, 7, 8, 9, 10) Piping Fiberglass Double Wall NOV Fiberglass Systems Red Thread IIA fiberglass piping
- (d) Product to be stored in each tank: (TK#6, 7) Gasoline, (TK#8) E-85, (TK#9, 10) Diesel Fuel
- (e) Type of leak detection being used:

Tank: (TK#6, 7, 8, 9, 10) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 450 with CSLD, (TK#6, 7, 8, 9, 10) Leak Detect - Tank - Hydrostatic Reservoir Sensors Interstitial Monitoring Veeder Root TLS 450 interstitial brine sensor, (TK#6, 7, 8, 9, 10) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 450

Piping: (TK#6, 7, 8, 9, 10) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 450, (TK#6, 7, 8, 9, 10) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 450

(f) Corrosion Protection being used:

Tank: (TK#6, 7, 8, 9, 10) Corrosion Prot - Tank - Fiberglass Non-Corrosive

Piping: (TK#6, 7, 8, 9, 10) Corrosion Prot - Piping - Fiberglass Non-Corrosive

- (g) Spill containment devices, piping and dispenser containment devices: (TK # 6, 7, 8, 9, 10) Spill Contain Device Pre-manufactured EBW 705 CIGKT Defender spill containment
- (h) Overfill prevention devices: (TK#6, 7, 8, 9, 10) Overfill Prev Device Ball Float Vent Valve OPW 53VML, (TK#6, 7, 8, 9, 10) Overfill Prev Device Overfill Drop Tube Valve EBW 708 Auto Limiter II, (TK#6, 7, 8, 9, 10) Overfill Prev Device Overfill Alarm Veeder Root TLS 450
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.govor by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS: There shall be a minimum of two manufactured slotted or perforated observation wells of at lease 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

(6) SPECIAL CONTINGENCIES:

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Stenstrom Petroleum Services Group

2422 Center Street Rockford, IL 61108 Contact Person: Robert Stenstrom

Phone: (815) 398-6250

Contractor Registration # IL1890 Exp. 3/7/2016

Sincerely,

Daniel Starks

Daniel J. Starke

cc: Storage Tank Safety Specialist Division File