



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)785-1020
Amended

FOR OFFICE USE ONLY
Facility # 4-015248
Permit # 00401-2015INS
Request Rec'd 05/11/2015
Amended Date 08/06/2015
Approval Date 5/11/2015 DS
Permit Expires 11/12/2015

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Baba Peer, LLC 4455 Ashbury Park Dr. Newburgh, IN 47630 Contact: Dilbag Singh (812) 305-1278	(2) FACILITY - name and address where tanks are located: Jumpin' Jimmy's 110 N. Houghton Hwy. Greenup, Cumberland Co., IL Contact: Annette Rowe (217) 923-5091
--	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed:** (TK # 8) - 10,000 gallons, (TK # 9) - 8,000 gallons, (TK # 10) - 4,000 gallons
- (b) Type of tanks:** (TK # 8, 9, 10) - (Installing) Composite Double Wall Glasteel II
- (c) Type of piping:** (TK # 8, 9, 10) - (Installing) Dispenser Sumps containment FRP, (TK # 8, 9, 10) - (Installing) Submersible Sumps containment FRP, (TK # 8, 9, 10) - (Installing) Fiberglass Double Wall Ameron Dualoy 3000/LCX
- (d) Product to be stored in each tank:** (TK # 8, 10) - Gasoline, (TK # 9) - Diesel Fuel
- (e) Type of leak detection being used:**
 - Tank:** (TK # 8, 9, 10) - (Installing) Interstitial Monitoring Veeder Root TLS 350, (TK # 8, 9, 10) - (Installing) Automatic Tank Gauging Veeder Root TLS 350
 - Piping:** (TK # 8, 9, 10) - (Installing) Mechanical Pressurized Line Leak Detection Red Jacket FX1, (TK # 8, 9, 10) - (Installing) Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350 in all dispenser and submersible sumps
- (f) Corrosion Protection being used:**
 - Tank:** (TK # 8, 9, 10) - (Installing) Composite Non-Corrosive
 - Piping:** (TK # 8, 9, 10) - (Installing) Fiberglass Non-Corrosive
- (g) Spill containment devices, piping and dispenser containment devices:** (TK # 8, 9, 10) - (Installing) Manhole Pre-manufactured OPW 1-2100
- (h) Overfill prevention devices:** (TK # 8, 9, 10) - (Installing) Overfill Drop Tube Valve OPW 71SO


(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.

(5) GENERAL REQUIREMENTS: There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

(6) SPECIAL CONTINGENCIES: Permit amended on 8/6/15 to change leak detection to TLS 350 and also PLLD from electronic to mechanical

(7) PERSON, FIRM OR COMPANY PERFORMING WORK: Hinderliter Construction & Maint., Inc. 3601 North St. Joseph Avenue Evansville, IN 47720	Contact Person: Mark Hinderliter Phone: (812) 425-4137 Contractor Registration # IL-646 Exp. 04/02/2016
--	---

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist -
Fire Department -
Division File
(Rev. - 9/10)