



Office of the Illinois State Fire Marshal
 Division of Petroleum and Chemical Safety
 1035 Stevenson Drive
 Springfield, IL 62703
 2177851020

FOR OFFICE USE ONLY
 Facility # 3046022
 Permit # 01183-2015INS
 Request Rec'd 10/26/2015
 Amended Date
 Approval Date 10/26/2015 DS
 Permit Expires 4/26/2016

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p>(1) OWNER OF TANKS - Corporation, partnership, or other business entity:</p> <p>Hy-Vee, Inc. 5820 Westown Parkway West Des Moines, IA 50266</p> <p>Contact: John Brummit (515) 267-2800</p>	<p>(2) FACILITY - name and address where tanks are located:</p> <p>Hy-Vee Gas 1925 N Henderson St Galesburg IL 61401</p> <p>Contact:</p>
---	---

(3) INSTALLATION OF TANKS:

- (a) *Number and size of tanks being installed: (TK # 1) - 20,000, (TK # 2) - 8,000, (TK # 3, 4, 5) - 6,000*
- (b) *Type of tank(s): (TK # 1, 2, 3, 4, 5) Tank - Fiberglass Double Wall XERXES*
- (c) *Type of piping: (TK # 1, 2, 3, 4, 5) Piping - Flexible Double Wall A.P.T. Poly Tech P175SC, (TK # 1, 2, 3, 4, 5) Piping - Dispenser Sumps containment FRP, (TK # 1, 2, 3, 4, 5) Piping - Submersible Sumps containment FRP*
- (d) *Product to be stored in each tank: (TK # 1, 2, 3) - Gasoline, (TK # 4) - Diesel Fuel, (TK # 5) - E-85*
- (e) *Type of leak detection being used:*
 - Tank: (TK # 1, 2, 3, 4, 5) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 450 Plus ATG, (TK # 1, 2, 3, 4, 5) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 450 Plus*
 - Piping: (TK # 1, 2, 3, 4, 5) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 450 Plus, (TK # 1, 2, 3, 4, 5) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 450 Plus*
- (f) *Corrosion Protection being used:*
 - Tank: (TK # 1, 2, 3, 4, 5) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
 - Piping: (TK # 1, 2, 3, 4, 5) Corrosion Prot - Piping - Flexible Non-Corrosive*
- (g) *Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3, 4, 5) Spill Contain Device - Pre-manufactured OPW ISC-2100DEVR spill containment manhole*
- (h) *Overfill prevention devices: (TK # 1, 2, 3, 4, 5) Overfill Prev Device - Overfill Drop Tube Valve OPW 71SO-410C overfill drop tube*

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.

(5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.


(6) SPECIAL CONTINGENCIES :

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Seneca Companies, Inc.
4140 East 14th Street PO Box 3360
Des Moines, IA 50313

Contact Person: Keri Hankins
Phone: (816) 761-1270
Contractor Registration # IL598 Exp. 2/23/2016

Sincerely,

A handwritten signature in cursive script that reads "Daniel G. Starks". The signature is written in black ink and is positioned above a horizontal line.

Daniel Starks

cc: Storage Tank Safety Specialist
Division File