



Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety  
1035 Stevenson Drive  
Springfield, IL 62703  
2177851020

**FOR OFFICE USE ONLY**

Facility # 1046099  
Permit # 00280-2016INS  
Request Rec'd 03/16/2016  
Amended Date  
Approval Date 3/17/2016 DS  
Permit Expires 9/19/2016

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p>(1) <b><u>OWNER OF TANKS</u></b> - Corporation, partnership, or other business entity:</p> <p>Casey's Retail Company P.O. Box 3001 One Convenience Blvd. SE Ankeny, IA 50021</p> <p>Contact: Jill Reams-Widder (515) 965-6238</p>	<p>(2) <b><u>FACILITY</u></b> - name and address where tanks are located:</p> <p>Casey General Stores 501 W. Market Street Shannon, IL 61078</p> <p>Contact: Jill Reams-widder (515) 965-6238</p>
--	---

**(3) INSTALLATION OF TANKS:**

- (a) *Number and size of tanks being installed: (TK # 1) - 20,000, (TK # 2) - 12,000, (TK # 3) - 8,000*
  - (b) *Type of tank(s): (TK # 1, 2, 3) Tank - Fiberglass Double Wall Containment Solutions*
  - (c) *Type of piping: (TK # 1, 2, 3) Piping - Flexible Double Wall A.P.T. Poly Tech P175SC, (TK # 1, 2, 3) Piping - Dispenser Sumps A.P.T. Poly Tech Polyethylene LM Series, (TK # 1, 2, 3) Piping - Submersible Sumps Franklin Fueling Systems A-4800 Series*
  - (d) *Product to be stored in each tank: (TK # 1, 3) - Gasoline, (TK # 2) - Diesel Fuel*
  - (e) *Type of leak detection being used:*
    - Tank: (TK # 1, 2, 3) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD, (TK # 1, 2, 3) Leak Detect - Tank - Non-Discriminating Sensors Interstitial Monitoring Veeder Root TLS 350 micro sensor*
    - Piping: (TK # 1, 2, 3) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 350 PLLD leak sensors, (TK # 1, 2, 3) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350 Plus in all submersible and dispenser sumps*
  - (f) *Corrosion Protection being used:*
    - Tank: (TK # 1, 2, 3) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
    - Piping: (TK # 1, 2, 3) Corrosion Prot - Piping - Flexible Non-Corrosive*
  - (g) *Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3) Spill Contain Device - Pre-manufactured EBW 705 CIGKT Defender spill containment*
  - (h) *Overfill prevention devices: (TK # 1, 2, 3) Overfill Prev Device - Overfill Drop Tube Valve OPW 71SO-410C overfill drop tube*
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at [www.sfm.illinois.gov](http://www.sfm.illinois.gov) by calling (217)785-1020.
- (5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion

protection.


- (6) **SPECIAL CONTINGENCIES** : Installing 2-20,000 UST's 1 being an 12/8 split compartment tank, 4 dispensers up front 2-3+0 and 2-3+1 encore 700s, Then Diesel dispenser in rear master and satilite.

(6) **PERSON, FIRM OR COMPANY PERFORMING WORK:**

Pipeco, Inc.  
610 29th Street  
Bettendorf, IA 52722

Contact Person: Debbie Rindler  
Phone: (563) 344-0700  
Contractor Registration # IL2034 Exp. 9/28/2016

Sincerely,

A handwritten signature in cursive script that reads "Daniel G. Starks". The signature is written in dark ink and is positioned above a horizontal line.

Daniel Starks

cc: Storage Tank Safety Specialist  
Division File