

#### Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 2177851020

## **FOR OFFICE USE ONLY**

Facility # 2024479 Permit # 00601-2016INS Request Rec'd 05/20/2016 Amended Date Approval Date 5/23/2016 DS Permit Expires 11/23/2016

## Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.** 

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business

entity:

Thornton's, Inc. 10101 Linn Station Road Louisville, KY 40223

Contact: Scott Roberts (800) 928-8022

(2) FACILITY - name and address where tanks are located:

Thornton Oil Corp. #003 7600 W. 159th Street Orland Park, IL 60462

Contact: Manager (708) 614-0377

#### (3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 6) 12,000
- (b) Type of tank(s): (TK # 6) Tank Fiberglass Double Wall Containment Solutions
- (c) Type of piping: (TK # 6) Piping Fiberglass Double Wall Ameron Dualoy 3000/LCX, (TK # 6) Piping Shear Valves, (TK # 6) Piping Valves Ball Valve, (TK # 6) Piping Submersible Sumps Containment Solutions Single Wall Fiberglass, (TK # 6) Piping Dispenser Sumps Bravo B-1000 Series, (TK # 6) Piping Flex Connector Steel
- (d) Product to be stored in each tank: (TK # 6) E-85
- (e) Type of leak detection being used:

Tank: (TK # 6) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD, (TK # 6) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 350 Plus

Piping: (TK # 6) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 350 PLLD leak sensors, (TK # 6) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350 Position sensitive sensor

(f) Corrosion Protection being used:

Tank: (TK # 6) Corrosion Prot - Tank - Fiberglass Non-Corrosive

Piping: (TK # 6) Corrosion Prot - Piping - Fiberglass Non-Corrosive

- (g) Spill containment devices, piping and dispenser containment devices: (TK # 6) Spill Contain Device Pre-manufactured EBW 705 C1GKT Defender spill containment
- (h) Overfill prevention devices: (TK # 6) Overfill Prev Device Overfill Drop Tube Valve EBW 708 Auto Limiter II, (TK # 6) Overfill Prev Device Overfill Alarm Veeder Root TLS 350 Plus
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.govor by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS: There shall be a minimum of two manufactured slotted or perforated observation wells of at lease 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping

is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

(6) <u>SPECIAL CONTINGENCIES</u>: Installing new 12,000 gallon double wall fiberglass tank for E-85. Installing new dispenser sumps, new Ameron LCX pipe. System to be monitored by existing Veeder Root.

# (6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Stenstrom Petroleum Services Group 2422 Center Street

Rockford, IL 61108

Contact Person: Nate Meyer Phone: (815) 398-6250

Contractor Registration # IL1890 Exp. 3/7/2018

Sincerely,

Daniel Starks

Daniel J. Starke

cc: Storage Tank Safety Specialist Division File