



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 4021638
Permit # 00741-2016INS
Request Rec'd 06/07/2016
Amended Date
Approval Date 6/20/2016 DS
Permit Expires 12/20/2016

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p>(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity:</p> <p>Jay Swami Food Mart, Inc. 5100 Hickory Point Frontage Road Decatur, IL 62526</p> <p>Contact: Vipul Patel (267) 261-8342</p>	<p>(2) <u>FACILITY</u> - name and address where tanks are located:</p> <p>Price Rite Food & Liquor 2195 N. Oakland Avenue Decatur, IL 62526</p> <p>Contact: Vipul Patel (217) 261-8342</p>
--	---

(3) INSTALLATION OF TANKS:

- (a) *Number and size of tanks being installed: (TK # 3) - 6,000, (TK # 4) - 4,000*
- (b) *Type of tank(s): (TK # 3, 4) Tank - Composite Double Wall Glasteel II*
- (c) *Type of piping: (TK # 3, 4) Piping - Flexible Double Wall A.P.T. Poly Tech S175SC, (TK # 3, 4) Piping - Shear Valves, (TK # 3, 4) Piping - Valves Ball Valve, (TK # 3, 4) Piping - Dispenser Sumps A.P.T. Poly Tech Polyethylene LM Series, (TK # 3, 4) Piping - Submersible Sumps Franklin Fueling Systems 4736 Series Polyethylene, (TK # 3, 4) Piping - Flex Connector Steel*
- (d) *Product to be stored in each tank: (TK # 3) - Gasoline, (TK # 4) - Diesel Fuel*
- (e) *Type of leak detection being used:*
 - Tank: (TK # 3, 4) Leak Detect - Tank - Automatic Tank Gauging Incon TS 750, (TK # 3, 4) Leak Detect - Tank - Interstitial Monitoring Incon TSP ULS*
 - Piping: (TK # 3, 4) Leak Detect - Piping - Mechanical Pressurized Line Leak Detection FE Petro STP-MLD, (TK # 3, 4) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Incon TSP ULS*
- (f) *Corrosion Protection being used:*
 - Tank: (TK # 3, 4) Corrosion Prot - Tank - Composite Non-Corrosive*
 - Piping: (TK # 3, 4) Corrosion Prot - Piping - Flexible Non-Corrosive*
- (g) *Spill containment devices, piping and dispenser containment devices: (TK # 3, 4) Spill Contain Device - Manhole Pre-manufactured OPW ISC-2100C 5 gallon*
- (h) *Overfill prevention devices: (TK # 3, 4) Overfill Prev Device - Overfill Drop Tube Valve OPW 71SO-4000 overfill drop tube valve*

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.

(5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion

protection.


- (6) **SPECIAL CONTINGENCIES** : Installing a new 10,000 gallon Glass Steel II double wall tank split 6k / 4k with deadmen tank anchors & (2) monitoring wells , reusing the Incon TS 750 tank monitor & probes, adding new Incon TSP-ULS sump & interstitial tank sensors. Installing new APT poly tank sumps with FE Petro submersibles , FE Petro Mechanical line leak detectors & ball valves . Installing new APT poly dispenser sumps with OPW 10P-0152 sheer valves & steel flexes. Installing New APT XP 175-SC DW flex piping & Ameron S/W vent piping. installing OPW # 1 5gal. spill containment manholes with OPW 71SO -4000 overfill drop tubes.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Seneca Companies, Inc.
4140 East 14th Street PO Box 3360
Des Moines, IA 50313

Contact Person: Keri Hankins
Phone: (816) 761-1270
Contractor Registration # IL598 Exp. 2/23/2018

Sincerely,

A handwritten signature in cursive script that reads "Daniel G. Starks". The signature is written in dark ink and is positioned above a horizontal line.

Daniel Starks

cc: Storage Tank Safety Specialist
Division File