



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Petroleum and Chemical Safety
 1035 Stevenson Drive
 Springfield, Illinois 62703-4259
 (217)785-1020

FOR OFFICE USE ONLY
 Facility # 3-045322
 Permit # 00238-2013INS
 Request Rec'd 03/26/2013
 Amended Date
 Approval Date 3/27/2013 JC
 Permit Expires 9/27/2013

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p>(1) OWNER OF TANKS - Corporation, partnership, or other business entity:</p> <p>Metrolink 1515 River Drive Moline, IL 61265</p> <p>Contact: Dan Payne (309) 786-3081</p>	<p>(2) FACILITY - name and address where tanks are located:</p> <p>Metrolink 4501 4th Ave. Rock Island, Rock Island Co., IL</p> <p>Contact: Dan Payne (309) 786-3081</p>
--	---

(3) INSTALLATION OF TANKS:

- (a) **Number and size of tanks being installed:** (TK # 1, 2) - 12,000 gallons
- (b) **Type of tanks:** (TK # 1, 2) - (Installing) Fiberglass Double Wall XERXES
- (c) **Type of piping:** (TK # 1, 2) - (Installing) Flexible Double Wall OPW Flexworks CA15-250 non corrosive product piping from the tanks to 3 dispensers, and to a generator (the generator will not be located inside of a building, and there will be a transition sump that will effectively transition the underground piping to above ground piping before it reaches the concrete generator pad). There will also be a siphon bar between these tanks for the equalization of the levels of the fuel between the two tanks. There will be a submersible pump in each tank.
- (d) **Product to be stored in each tank:** (TK # 1, 2) - Diesel Fuel
- (e) **Type of leak detection being used:**
 - Tank:** (TK # 1, 2) - (Installing) Interstitial Monitoring Veeder Root TLS 350R , (TK # 1, 2) - (Installing) Automatic Tank Gauging Veeder Root TLS 350R with CSLD
 - Piping:** (TK # 1, 2) - (Installing) Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350R at each dispenser sump and at each submersible sump , (TK # 1, 2) - (Installing) Electronic Pressurized Line Leak Detection Veeder Root TLS 350R
- (f) **Corrosion Protection being used:**
 - Tank:** (TK # 1, 2) - (Installing) Fiberglass Non-Corrosive
 - Piping:** (TK # 1, 2) - (Installing) Flexible Non-Corrosive
- (g) **Spill containment devices, piping and dispenser containment devices:** (TK # 1, 2) - (Installing) Manhole Pre-manufactured OPW 1C-2100-DEVR
- (h) **Overfill prevention devices:**

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.

(5) GENERAL REQUIREMENTS: There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

(6) SPECIAL CONTINGENCIES:

<p>(7) PERSON, FIRM OR COMPANY PERFORMING WORK:</p> <p align="right">Contact Person: Tony Cooper Phone: (319) 377-6357 Contractor Registration # IL-612 Exp. 10/06/2013</p>
--

Sincerely,

James J. Coffey

cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 9/10)