



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
 1035 Stevenson Drive
 Springfield, Illinois 62703-4259
 (217)524-7605
Extended

<u>FOR OFFICE USE ONLY</u>
Facility # 2-011030
Permit # 01314-2008INS
Request Rec'd 08/05/2008
Amended Date
Approval Date 8/6/2008 JC
Permit Expires 8/6/2009

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p>(1) OWNER OF TANKS - Corporation, partnership, or other business entity:</p> <p>Exxon Mobil Oil Corporation 7300 West Friendly Avenue, P.O. Box 22087, CMS Mailstop F-76 Greensboro, NC 27420-2087 Contact: Eric McPhee (800) 253-8054</p>	<p>(2) FACILITY - name and address where tanks are located:</p> <p>Mobil Oasis Eastbound / Northbound 4100 Denley Road, Tri-State Toll I-294 Mile Post 38.0 Schiller Park, Cook Co., IL Contact: Eric McPhee (303) 986-8011</p>
---	---

(3) INSTALLATION OF TANKS:

- (a) **Number and size of tanks being installed:** (TK # 2579) - 10,000 gallons
- (b) **Type of tanks:** (TK # 2579) - (Installing) Fiberglass Brine Filled Double Wall Containment Solutions
- (c) **Type of piping:** (TK # 2579) - (Installing) Chase Secondary Containment OPW Geoduct non-corrosive flexible secondary piping, (TK # 2579) - (Installing) Flexible Double Wall OPW Flexworks CP-15 non corrosive
- (d) **Product to be stored in each tank:** (TK # 2579) - E-85
- (e) **Type of leak detection being used:**
 - Tank:** (TK # 2579) - (Installing) Automatic Tank Gauging Veeder Root TLS 350 Plus , (TK # 2579) - (Installing) Hydrostatic Reservoir Sensors Interstitial Monitoring Veeder Root TLS 350
 - Piping:** (TK # 2579) - (Installing) Electronic Pressurized Line Leak Detection Veeder Root TLS 350 , (TK # 2579) - (Installing) Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350 mag
- (f) **Corrosion Protection being used:**
 - Tank:** (TK # 2579) - (Installing) Fiberglass Non-Corrosive
 - Piping:** (TK # 2579) - (Installing) Impressed Current Cathodic Protection , (TK # 2579) - (Installing) Non-Corrosive Flexible Non-Corrosive
- (g) **Spill containment devices:** (TK # 2579) - (Installing) Manhole Pre-manufactured OPW 521 multi - port
- (h) **Overfill prevention devices:**

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

<p>(7) PERSON, FIRM OR COMPANY PERFORMING WORK:</p> <p align="right">Contact Person: Phone: (708) 758-3222 Contractor Registration # IL-194 Exp. 06/21/2010</p>
--

Sincerely,

