



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 1046356
Permit # 00298-2017INS
Request Rec'd 03/16/2017
Amended Date
Approval Date 3/16/2017 DS
Permit Expires 9/18/2017

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity: Western Trail Outpost, LLC 9673 Somanauk Rd. Hinckley, IL 60520 Contact: Randy Carls (815) 286-3281	(2) <u>FACILITY</u> - name and address where tanks are located: The Outpost 439 E. State St. Sycamore, IL 60178 Contact: Randy Carls (815) 286-3281
---	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 1) - 8,000, (TK # 2) - 12,000, (TK # 3) - 20,000*
- (b) Type of tank(s): (TK # 1, 2, 3) Tank - Fiberglass Double Wall Containment Solutions*
- (c) Type of piping: (TK # 1, 2, 3) Piping - Fiberglass Double Wall Ameron Dualoy 3000/LCX, (TK # 1, 2, 3) Piping - Fiberglass Secondary Containment Ameron, (TK # 1, 2, 3) Piping - Shear Valves, (TK # 1, 2, 3) Piping - Dispenser Sumps OPW DS-1000 Series, (TK # 1, 2, 3) Piping - Submersible Sumps OPW Flexworks Poly Sump*
- (d) Product to be stored in each tank: (TK # 1, 3) - Gasoline, (TK # 2) - Diesel Fuel*
- (e) Type of leak detection being used:*
 - Tank: (TK # 1, 2, 3) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 450 Plus*
 - Piping: (TK # 1, 2, 3) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 450 Plus, (TK # 1, 2, 3) Leak Detect - Piping - Pressurized Line Leak Detection, (TK # 1, 2, 3) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 450 Plus*
- (f) Corrosion Protection being used:*
 - Tank: (TK # 1, 2, 3) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
 - Piping: (TK # 1, 2, 3) Corrosion Prot - Piping - Fiberglass Non-Corrosive*
- (g) Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3) Spill Contain Device - Manhole Pre-manufactured OPW 1-2100*
- (h) Overfill prevention devices: (TK # 1, 2, 3) Overfill Prev Device - Overfill Alarm Veeder Root TLS 450plus*

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.

(5) GENERAL REQUIREMENTS : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion

protection.

(6) SPECIAL CONTINGENCIES :

The scope of work consists of the installation of (1) new Containment Solutions double wall 2 compartment (8,000 / 12,000) tank and (1) new Containment Solutions 20,000 gallon double wall tank. Both tanks will have a dry interstitial space. The tank and line monitoring will be a Veeder-Root TLS 450plus with a #794390-409 dry interstitial sensors and Veeder-Root #794380-208 piping sump sensors installed in all tank and dispenser sumps. There will be Veeder-Root #859080-002 Digital Pressurized Line Leak Detectors installed in all sub pumps.

The spill prevention will be OPW 1-2100 spill containers. The overfill prevention will be a Veeder-Root #790091 overfill alarm.


The piping will be 2" Ameron/NOV LCX double wall frp pipe.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Illinois Oil Marketing Equipment, Inc.
850 Brenkman Drive
Pekin, IL 61554

Contact Person: Chris Epkins
Phone: (309) 347-1819
Contractor Registration # IL1293 Exp. 2/4/2018

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist
Division File