



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 7023232
Permit # 00719-2017INS
Request Rec'd 06/14/2017
Amended Date
Approval Date 6/19/2017 DS
Permit Expires 12/19/2017

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p>(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity:</p> <p>Shree Vasudev 1, LLC 105 W. Main Street Ridgway, IL 62979 Contact: (618) 272-5303</p>	<p>(2) <u>FACILITY</u> - name and address where tanks are located:</p> <p>Ridgeway Quick Mart 105 Main Street Ridgway, IL 62979 Contact: Peter Patel (812) 205-8505</p>
---	---

(3) INSTALLATION OF TANKS:

- (a) *Number and size of tanks being installed: (TK # 3) - 7,000, (TK # 4) - 3,000*
- (b) *Type of tank(s): (TK # 3, 4) Tank - Jacketed Steel Double Wall*
- (c) *Type of piping: (TK # 3, 4) Piping - Fiberglass Double Wall Ameron Dualoy 3000/LCX, (TK # 3, 4) Piping - Other Steel Riser, (TK # 3, 4) Piping - Other submersible pump, (TK # 3, 4) Piping - Shear Valves, (TK # 3, 4) Piping - Dispenser Sumps Petroleum Containment Inc. CLE/CLS Dispenser Sump Conduitless Entry Sump, (TK # 3, 4) Piping - Submersible Sumps Petroleum Containment Inc. 4500 Series, (TK # 3, 4) Piping - Flex Connector Steel*
- (d) *Product to be stored in each tank: (TK # 3) - Gasoline, (TK # 4) - Diesel Fuel*
- (e) *Type of leak detection being used:*
Tank: (TK # 3, 4) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350, (TK # 3, 4) Leak Detect - Tank - Non-Discriminating Sensors Interstitial Monitoring Veeder Root TLS 350 micro sensor
Piping: (TK # 3, 4) Leak Detect - Piping - Mechanical Pressurized Line Leak Detection Red Jacket FXIV, (TK # 3, 4) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350 in submersible and dispenser sumps
- (f) *Corrosion Protection being used:*
Tank: (TK # 3, 4) Corrosion Prot - Tank - Jacketed Steel Non-Corrosive
Piping: (TK # 3, 4) Corrosion Prot - Piping - Other dispenser containment sump, (TK # 3, 4) Corrosion Prot - Piping - Fiberglass Non-Corrosive
- (g) *Spill containment devices, piping and dispenser containment devices: (TK # 3, 4) Spill Contain Device - Manhole Pre-manufactured Emco Wheaton A1004*
- (h) *Overfill prevention devices: (TK # 3, 4) Overfill Prev Device - Overfill Drop Tube Valve Emco Wheaton A1100 Guardian*

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.

(5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut

off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.


(6) SPECIAL CONTINGENCIES :

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Hinderliter Construction & Maint., Inc.
3601 North St. Joseph Avenue
Evansville, IN 47720

Contact Person: Mark Hinderliter
Phone: (812) 425-4137
Contractor Registration # IL646 Exp. 4/2/2018

Sincerely,

A handwritten signature in dark ink, reading "Daniel H. Starks", is written over a horizontal line.

Daniel Starks

cc: Storage Tank Safety Specialist
Division File