



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 7046469
Permit # 01074-2017INS
Request Rec'd 08/28/2017
Amended Date
Approval Date 8/29/2017 DS
Permit Expires 2/28/2018

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Casey's Retail Company 3305 SE Delaware Avenue P.O. Box 3001 Ankeny, IA 50021 Contact: Jill Reams-Widder (515) 965-6238	(2) FACILITY - name and address where tanks are located: Casey's General Stores Inc 400 E. Deyoung St. Marion, IL 62959 Contact: Jill Reams-Widder (515) 965-6238
---	--

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 1) - 22,000, (TK # 2) - 14,000, (TK # 3, 4, 5) - 8,000**
- (b) Type of tank(s): (TK # 1, 2, 3, 4, 5) Tank - Fiberglass Double Wall XERXES**
- (c) Type of piping: (TK # 1, 2, 3, 4, 5) Piping - Flexible Double Wall A.P.T. Poly Tech PI75SC, (TK # 1, 2, 3, 4, 5) Piping - Shear Valves , (TK # 1, 2, 3, 4, 5) Piping - Submersible Sumps Franklin Fueling Systems A-4200 Series**
- (d) Product to be stored in each tank: (TK # 1, 3, 4, 5) - Gasoline, (TK # 2) - Diesel Fuel**
- (e) Type of leak detection being used:**

Tank: (TK # 1, 2, 3, 4, 5) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 350 , (TK # 1, 2, 3, 4, 5) Leak Detect - Tank - Non-Discriminating Sensors Interstitial Monitoring Veeder Root TLS 350 micro sensor

Piping: (TK # 1, 2, 3, 4, 5) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root Pressurized , (TK # 1, 2, 3, 4, 5) Leak Detect - Piping - Sump Sensors Interstitial Monitoring Veeder Root TLS 350 interstitial piping float sensor in all submersible and dispenser sumps

- (f) Corrosion Protection being used:**

Tank: (TK # 1, 2, 3, 4, 5) Corrosion Prot - Tank - Fiberglass Non-Corrosive

Piping: (TK # 1, 2, 3, 4, 5) Corrosion Prot - Piping - Flexible Non-Corrosive

- (g) Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3, 4, 5) Spill Contain Device - Manhole Pre-manufactured EBW 705**

- (h) Overfill prevention devices: (TK # 1, 2, 3, 4, 5) Overfill Prev Device - Overfill Drop Tube Valve OPW 71SO**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.**
- (5) GENERAL REQUIREMENTS :** There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion

protection.

(6) SPECIAL CONTINGENCIES : Scope of work will be the installation of (2) new Xerxes double wall compartment tanks, one will be a (2) compartment 22,000/8,000 and one will be a (3) compartment 14,000/8,000/8,000. There will be (6) new dispensers installed with a canopy.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Illinois Oil Marketing Equipment, Inc.
850 Brenkman Drive
Pekin, IL 61554

Contact Person: Chris Epkins
Phone: (309) 347-1819
Contractor Registration # IL1293 Exp. 2/4/2018

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist
Division File