



Office of the Illinois State Fire Marshal  
Division of Petroleum and Chemical Safety  
1035 Stevenson Drive  
Springfield, IL 62703  
2177851020

**FOR OFFICE USE ONLY**

Facility # 2046091  
Permit # 01167-2017INS  
Request Rec'd 09/20/2017  
Amended Date  
Approval Date 9/20/2017 DS  
Permit Expires 3/20/2018

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

|  |   |
|--|---|
| <p>(1) <b>OWNER OF TANKS</b> - Corporation, partnership, or other business entity:</p> <p>Progressive Petroleum, LLC<br/>1701 E. Woodfield Road, Suite 327<br/>Schaumburg IL 60173<br/>Contact: Farrukh Bagasra (847) 845-4051</p> | <p>(2) <b>FACILITY</b> - name and address where tanks are located:</p> <p>Hoffman Estates Gas<br/>S.E. Corner of Hoffman Blvd &amp; Old Sutton Road<br/>Hoffman Estates, IL 60192<br/>Contact: Farrukh Bagasra (847) 845-4051</p> |
|--|---|

**(3) INSTALLATION OF TANKS:**

- (a) *Number and size of tanks being installed: (TK # 1, 3) - 6,000, (TK # 2) - 12,000*
- (b) *Type of tank(s): (TK # 1, 2, 3) Tank - Fiberglass Double Wall XERXES*
- (c) *Type of piping: (TK # 1, 2, 3) Piping - Fiberglass Double Wall Ameron Dualoy 3000/LCX, (TK # 1, 2, 3) Piping - Other submersible pump, (TK # 1, 2, 3) Piping - Positive Shutoff Valves, (TK # 1, 2, 3) Piping - Shear Valves, (TK # 1, 2, 3) Piping - Valves Ball Valve, (TK # 1, 2, 3) Piping - Submersible Sumps XERXES Fiberglass, (TK # 1, 2, 3) Piping - Flex Connector Steel*
- (d) *Product to be stored in each tank: (TK # 1, 2) - Gasoline, (TK # 3) - Diesel Fuel*
- (e) *Type of leak detection being used:*
  - Tank: (TK # 1, 2, 3) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350 Plus, (TK # 1, 2, 3) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 350 Plus*
  - Piping: (TK # 1, 2, 3) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 350 PLLD leak sensors, (TK # 1, 2, 3) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350 Plus in all submersible and dispenser sumps*
- (f) *Corrosion Protection being used:*
  - Tank: (TK # 1, 2, 3) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
  - Piping: (TK # 1, 2, 3) Corrosion Prot - Piping - Fiberglass Non-Corrosive*
- (g) *Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3) Spill Contain Device - Pre-manufactured Emco Wheaton EBW 705 Defender II*
- (h) *Overfill prevention devices: (TK # 1, 2, 3) Overfill Prev Device - Overfill Alarm Veeder Root TLS 350 Plus*

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at [www.sfm.illinois.gov](http://www.sfm.illinois.gov) by calling (217)785-1020.

(5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping

is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.


**(6) SPECIAL CONTINGENCIES :**

**(6) PERSON, FIRM OR COMPANY PERFORMING WORK:**

Crowne Industries, Ltd.  
651 S. Sutton Road #214  
Streamwood, IL 60107

Contact Person: Robert Sumoski  
Phone: (630) 497-9009  
Contractor Registration # IL002345 Exp. 5/16/2018

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist  
Division File