



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 1009877
Permit # 01326-2017INS
Request Rec'd 07/03/2017
Amended Date
Approval Date 10/23/2017 DS
Permit Expires 4/24/2018

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity: A 33 Milestone Gas & Food, Inc. II 2627 Auburn Street Rockford, IL 61103 Contact: Anthony Virk (815) 708-7081	(2) <u>FACILITY</u> - name and address where tanks are located: A 33 Milestone Gas & Food, Inc. II 2627 Auburn Street Rockford, IL 61103 Contact: Kathleen Schelm (815) 708-7081
---	--

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 3) - 12,000, (TK # 4) - 4,000*
- (b) Type of tank(s): (TK # 3, 4) Tank - Fiberglass Double Wall XERXES*
- (c) Type of piping: (TK # 3, 4) Piping - Fiberglass Double Wall Ameron Dualoy 3000/LCX, (TK # 3, 4) Piping - Fiberglass Secondary Containment Ameron, (TK # 3, 4) Piping - Shear Valves, (TK # 3, 4) Piping - Valves Ball Valve, (TK # 3, 4) Piping - Dispenser Sumps Bravo B-1000 Series, (TK # 3, 4) Piping - Flex Connector Steel*
- (d) Product to be stored in each tank: (TK # 3, 4) - Gasoline*
- (e) Type of leak detection being used:*
 - Tank: (TK # 3, 4) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350, (TK # 3, 4) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 350*
 - Piping: (TK # 3, 4) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 350, (TK # 3, 4) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350*
- (f) Corrosion Protection being used:*
 - Tank: (TK # 3, 4) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
 - Piping: (TK # 3, 4) Corrosion Prot - Piping - Other dispenser containment sump, (TK # 3, 4) Corrosion Prot - Piping - Fiberglass Non-Corrosive*
- (g) Spill containment devices, piping and dispenser containment devices: (TK # 3, 4) Spill Contain Device - Manhole Pre-manufactured OPW 1C-2100C-DEVR*
- (h) Overfill prevention devices: (TK # 3, 4) Overfill Prev Device - Overfill Drop Tube Valve OPW 71SO*

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.

(5) GENERAL REQUIREMENTS : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping

is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.


- (6) **SPECIAL CONTINGENCIES** : Install one multicompartment tank 12,000/ 4,000 split double wall fiberglass tank with interstitial sensor. Installing all new product piping in existing trenches, Ameron LCX 2"; installing all new vent line, Ameron LX 2". Installing three single wall fiberglass dispenser sump and two single wall fiberglass tank sumps. Install Veeder Root TLS 350 with two Mag-Plus Probes and five non-discriminating sump sensors. Install OPW 1c-2100c series spill buckets with 71SO series overfill prevention drop tubes.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Stenstrom Petroleum Services Group
2422 Center Street
Rockford, IL 61108

Contact Person: Nate Meyer
Phone: (815) 398-6250
Contractor Registration # IL1890 Exp. 3/7/2018

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist
Division File