



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 2046509
Permit # 00554-2018INS
Request Rec'd 04/29/2018
Amended Date
Approval Date 5/7/2018 DS
Permit Expires 11/8/2018

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity: Orchards Lot 6, LLC 1375 Remington Rd Suite E Schaumburg IL 60173 Contact: Rana Hamid (847) 361-7720	(2) <u>FACILITY</u> - name and address where tanks are located: Orchards 3003 Mannheim Rd. Des Plaines, IL 60018 Contact: Rana Hamid (847) 361-7720
--	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 1) - 20,000, (TK # 2, 3) - 10,000, (TK # 4) - 6,000*
 - (b) Type of tank(s): (TK # 1, 2, 3, 4) Tank - Fiberglass Double Wall XERXES*
 - (c) Type of piping: (TK # 1, 2, 3, 4) Piping - Fiberglass Double Wall Ameron Dualoy 3000/LCX, (TK # 1, 2, 3, 4) Piping - Extractor Fitting Valves, (TK # 1, 2, 3, 4) Piping - Shear Valves, (TK # 1, 2, 3, 4) Piping - Valves Ball Valve, (TK # 1, 2, 3, 4) Piping - Flex Connector Steel*
 - (d) Product to be stored in each tank: (TK # 1, 4) - Gasoline, (TK # 2) - E-85, (TK # 3) - Diesel Fuel*
 - (e) Type of leak detection being used:*
 - Tank: (TK # 1, 2, 3, 4) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350 Plus with CSLD, (TK # 1, 2, 3, 4) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 350 Plus*
 - Piping: (TK # 1, 2, 3, 4) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 350 PLLD leak sensors, (TK # 1, 2, 3, 4) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350*
 - (f) Corrosion Protection being used:*
 - Tank: (TK # 1, 2, 3, 4) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
 - Piping: (TK # 1, 2, 3, 4) Corrosion Prot - Piping - Fiberglass Non-Corrosive*
 - (g) Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3, 4) Spill Contain Device - Manhole Pre-manufactured Franklin Fueling Systems Defender 705 Double Wall*
 - (h) Overfill prevention devices: (TK # 1, 2, 3, 4) Overfill Prev Device - Overfill Drop Tube Valve OPW 71SO-410C overfill drop tube*
- (4)** The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion

protection.

(6) **SPECIAL CONTINGENCIES :**

Installing New Double wall Xerxes tanks (Installed under permit number 01303-2017INS that expired before piping completed)

Installing new Lcx double wall piping, Bravo single wall sumps with sump sensors, Fe petro submersible's, Plld leakdetectors, Tls monitor

Product in compartment tank will be 10k E85 6k Diesel, 10K Premium, 20k Regular.


Installing new canopy with raised islands with u shape collision protection.

(6) **PERSON, FIRM OR COMPANY PERFORMING WORK:**

Efficiency Petroleum Service
200 W. Higgins Ste 326
Schaumburg, IL 60195

Contact Person: Dana Scott
Phone: (630) 486-8408
Contractor Registration # IL002425 Exp. 8/24/2019

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist
Division File