



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

Amended

FOR OFFICE USE ONLY

Facility # 3046631
Permit # 00606-2018INS
Request Rec'd 05/15/2018
Amended Date 06/11/2018 DS
Approval Date 5/16/2018 DS
Permit Expires 11/16/2018

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity: Gold Star FS, Inc. 101 North East St. Cambridge, IL 61238 Contact: Greg Rohman (309) 937-3369	(2) <u>FACILITY</u> - name and address where tanks are located: Goldstar FS 1000 S. E. 2nd Street Galva, IL 61434 Contact: Greg Rohman (309) 738-3384
---	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 1) - 22,000, (TK # 2) - 8,000, (TK # 3, 4) - 10,000*
- (b) Type of tank(s): (TK # 1, 2, 3, 4) Tank - Fiberglass Double Wall Containment Solutions*
- (c) Type of piping: (TK # 1, 2, 3, 4) Piping - Fiberglass Single Wall Piping Ameron Dualoy 3000L single wall fiberglass piping, (TK # 1, 2, 3, 4) Piping - Steel Single Wall Piping, (TK # 1, 2, 3, 4) Piping - Flexible Double Wall A.P.T. Poly Tech S175SC, (TK # 1, 2, 3, 4) Piping - Submersible Sumps Petroleum Containment Inc. 4200 Series Single Wall*
- (d) Product to be stored in each tank: (TK # 1) - Diesel Fuel, (TK # 2) - Diesel Exhaust Fluid (Non-Regulated), (TK # 3) - Gasoline, (TK # 4) - E-85*
- (e) Type of leak detection being used:*
 - Tank: (TK # 1, 2, 3, 4) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD, (TK # 1, 2, 3, 4) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 450 Plus*
 - Piping: (TK # 1, 2, 3, 4) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 450 Plus 8590 DPLLD, (TK # 1, 2, 3, 4) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 450 Plus*
- (f) Corrosion Protection being used:*
 - Tank: (TK # 1, 2, 3, 4) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
 - Piping: (TK # 1, 2, 3, 4) Corrosion Prot - Piping - Flexible Non-Corrosive*
- (g) Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3, 4) Spill Contain Device - Manhole Pre-manufactured OPW 1C-3112D Edge Double Wall*
- (h) Overfill prevention devices: (TK # 1, 2, 3, 4) Overfill Prev Device - Other OPW 61F, (TK # 1, 2, 3, 4) Overfill Prev Device - Overfill Alarm Veeder Root TLS 450plus*

- (4)** The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.

- (5) GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut

off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

(6) SPECIAL CONTINGENCIES :


After site layout was complete it was determined with the required retention pond that having the shed on the far west end of the tank pad created a significant restriction in the truck turn radius and the delivery drivers would struggle to get around the pad, we are presenting a new site plan that eliminates the shed extension by rotating the shed to un-utilized section of hard surface on the west end of the 20K tank. If questions please give me a call. Thank you Glen 563-340-5216

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Seneca Companies, Inc.
4140 East 14th Street PO Box 3360
Des Moines, IA 50313

Contact Person: Keri Hankins
Phone: (816) 761-1270
Contractor Registration # IL598 Exp. 2/23/2020

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist
Division File