



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 3046654
Permit # 00825-2018INS
Request Rec'd 06/29/2018
Amended Date
Approval Date 7/2/2018 DS
Permit Expires 1/2/2019

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity: NF Properties, LLC P.O. Box C-847 Quincy, IL 62305 Contact: Andy Hermsmeier (217) 221-5770	(2) <u>FACILITY</u> - name and address where tanks are located: Niemann Foods- County Market Fuel 1106 N. 6th Street Monmouth, IL 61462 Contact: Andy Hermsmeier (217) 221-5628
--	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 1) - 20,000, (TK # 2, 3) - 6,000*
 - (b) Type of tank(s): (TK # 1, 2, 3) Tank - Fiberglass Double Wall XERXES*
 - (c) Type of piping: (TK # 1, 2, 3) Piping - Flexible Double Wall A.P.T. Poly Tech P175SC, (TK # 1, 2, 3) Piping - Other submersible pump, (TK # 1, 2, 3) Piping - Submersible Sumps XERXES Fiberglass Single Wall*
 - (d) Product to be stored in each tank: (TK # 1, 2) - Gasoline, (TK # 3) - Diesel Fuel*
 - (e) Type of leak detection being used:*
 - Tank: (TK # 1, 2, 3) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD, (TK # 1, 2, 3) Leak Detect - Tank - Ground Water Monitoring Wells, (TK # 1, 2, 3) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 450 Plus*
 - Piping: (TK # 1, 2, 3) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 450 Plus 8590 DPLLD, (TK # 1, 2, 3) Leak Detect - Piping - Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 450 Plus in all submersible and dispenser sumps. NOTE: All sensors must shut down the submersible supplying that line upon detection of a leak per 175.640 a) 2)*
 - (f) Corrosion Protection being used:*
 - Tank: (TK # 1, 2, 3) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
 - Piping: (TK # 1, 2, 3) Corrosion Prot - Piping - Fiberglass Non-Corrosive, (TK # 1, 2, 3) Corrosion Prot - Piping - Flexible Non-Corrosive*
 - (g) Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3) Spill Contain Device - Manhole Pre-manufactured OPW 1C-3112D Edge Double Wall*
 - (h) Overfill prevention devices: (TK # 1, 2, 3) Overfill Prev Device - Overfill Drop Tube Valve OPW 71SO-410C overfill drop tube*
- (4)** The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All

steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.


(6) SPECIAL CONTINGENCIES :

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Seneca Companies, Inc.
4140 East 14th Street PO Box 3360
Des Moines, IA 50313

Contact Person: Keri Hankins
Phone: (816) 761-1270
Contractor Registration # IL598 Exp. 2/23/2020

Sincerely,

A handwritten signature in cursive script that reads "Daniel H. Starks". The signature is written in dark ink and is positioned above a horizontal line.

Daniel Starks

cc: Storage Tank Safety Specialist
Division File