



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL  
Division of Technical Services  
1035 Stevenson Drive  
Springfield, Illinois 62703-4259  
(217)524-7605

FOR OFFICE USE ONLY  
Facility # 6-029334  
Permit # 01530-2008INS  
Request Rec'd 09/04/2008  
Amended Date  
Approval Date 9/4/2008 JC  
Permit Expires 3/4/2009

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>(1) OWNER OF TANKS</b> - Corporation, partnership, or other business entity:  Midwest Petroleum Company, Inc. 6760 Southwest Avenue St. Louis, MO 63143  Contact: Mike McNutt (314) 647-5550 Ext. 313	<b>(2) FACILITY</b> - name and address where tanks are located:  MPC #58 4001 South State Route 159 Glen Carbon, Madison Co., IL  Contact: Chuck Keller (800) 747-3777
--	--

**(3) INSTALLATION OF TANKS:**

- (a) Number and size of tanks being installed:** (TK # 4) - 20,000 gallons, and one compartment tank consisting of: (TK # 5, 6) - 6,000 gallons, (TK # 7) - 8,000 gallons
- (b) Type of tanks:** (TK # 4, 5, 6, 7) - (Installing) Glasteel II double wall composite
- (c) Type of piping:** (TK # 4, 5, 6, 7) - (Installing) A.P.T. Poly Tech P150SC double wall flexible
- (d) Product to be stored in each tank:** (TK # 4, 6) - Gasoline, (TK # 5) - E-85, (TK # 7) - Diesel Fuel
- (e) Type of leak detection being used:**
  - Tank:** (TK # 4, 5, 6, 7) - (Installing) Veeder Root TLS 350 interstitial tank sensor, (TK # 4, 5, 6, 7) - (Installing) Veeder Root TLS350 automatic tank gauge
  - Piping:** (TK # 4, 5, 6, 7) - (Installing) Veeder Root TLS350 interstitial piping sump sensors at all submersible sumps and all dispenser sumps, (TK # 4, 5, 6, 7) - (Installing) Veeder Root TLS350 electronic line leak detector
- (f) Corrosion Protection being used:**
  - Tank:** (TK # 4, 5, 6, 7) - (Installing) Composite
  - Piping:** (TK # 4, 5, 6, 7) - (Installing) Non-corrosive flexible
- (g) Spill containment devices:**
- (h) Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at [www.state.il.us/osfm](http://www.state.il.us/osfm) or by calling (217)785-1020.**

**(5) GENERAL REQUIREMENTS:**

**(6) SPECIAL CONTINGENCIES:**

<b>(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u></b>          Contact Person: Phil Parker Phone:  Contractor Registration # IL-2154 Exp. 03/21/2010
--

Sincerely,

cc: Storage Tank Safety Specialist -  
Fire Department -  
Office Coordinator -  
Division File  
(Rev. - 1/98)