



**OFFICE OF THE ILLINOIS STATE FIRE MARSHAL**  
**Division of Technical Services**  
 1035 Stevenson Drive  
 Springfield, Illinois 62703-4259  
 (217)524-7605

<u>FOR OFFICE USE ONLY</u>
Facility # 2-044173
Permit # 01502-2008INS
Request Rec'd 08/29/2008
Amended Date
Approval Date 8/29/2008 JC
Permit Expires 2/28/2009

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p><b>(1) OWNER OF TANKS</b> - Corporation, partnership, or other business entity:</p> <p>Knight Transportation          5601 West Buckeye Road          Phoenix, AZ 85043</p> <p>Contact:</p>	<p><b>(2) FACILITY</b> - name and address where tanks are located:</p> <p>Knight Transportation          3301 Mound Road          Joliet, Will Co., IL</p> <p>Contact:</p>
--	--

**(3) INSTALLATION OF TANKS:**

- (a) Number and size of tanks being installed:* (TK # 1) - 20,000 gallons, (TK # 2) - 2,500 gallons
- (b) Type of tanks:* (TK # 1) - (Installing) XERXES double wall fiberglass brine filled
- (c) Type of piping:* (TK # 1) - (Installing) Ameron Dualoy 3000/LCX double wall fiberglass
- (d) Product to be stored in each tank:* (TK # 1) - Diesel Fuel, (TK # 2) - Non Regulated
- (e) Type of leak detection being used:*
  - Tank:** (TK # 1) - (Installing) Veeder Root TLS 350 hydrostatic reservoir sensor, (TK # 1) - (Installing) Veeder Root TLS350 automatic tank gauge
  - Piping:** (TK # 1) - (Installing) Veeder Root TLS350 electronic line leak detector, (TK # 1) - (Installing) Veeder Root TLS350 interstitial piping sump sensors at the submersible sump and at all dispenser sumps.
- (f) Corrosion Protection being used:*
  - Tank:** (TK # 1) - (Installing) Fiberglass
  - Piping:** (TK # 1) - (Installing) Fiberglass
- (g) Spill containment devices:*
- (h) Overfill prevention devices:*

**(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at [www.state.il.us/osfm](http://www.state.il.us/osfm) or by calling (217)785-1020.**

**(5) GENERAL REQUIREMENTS:**

**(6) SPECIAL CONTINGENCIES:**

<p><b>(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u></b></p>	<p>Contact Person: Jim Veverka          Phone:          Contractor Registration # IL-1733 Exp. 02/21/2010</p>
---	---

Sincerely,

*James J. Coffey*

cc: Storage Tank Safety Specialist -  
 Fire Department -  
 Office Coordinator -  
 Division File  
 (Rev. - 1/98)