

Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 2177851020

Extended

FOR OFFICE USE ONLY

Facility # 2046729 Permit # 01562-2018INS Request Rec'd 10/16/2018 Amended Date Approval Date 10/16/2018 DS Permit Expires 10/16/2019

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity:

Vequity LLC Series XL Crystal Lake

400 N State St. Chicago, IL 60654

Contact: Ivan Nockov (773) 627-3116

(2) FACILITY - name and address where tanks are located:

Vequity LLC Series XL Crystal Lake 11 E Northwest Highway Crystal Lake, IL 60014

Contact: Ivan Nockov (773) 627-3116

(3) <u>INSTALLATION OF TANKS:</u>

- (a) Number and size of tanks being installed: (TK # 1) 20,000, (TK # 2) 8,000, (TK # 3) 12,000
- (b) Type of tank(s): (TK # 1, 2, 3) Tank Fiberglass Double Wall XERXES
- (c) Type of piping: (TK # 1, 2, 3) Piping Flexible Double Wall OPW Flexworks, (TK # 1, 2, 3) Piping Other Steel Riser, (TK # 1, 2, 3) Piping Other submersible pump, (TK # 1, 2, 3) Piping Chase Secondary Containment OPW AXP 4" secondary chase piping, (TK # 1, 2, 3) Piping Ball Valves, (TK # 1, 2, 3) Piping Shear Valves, (TK # 1, 2, 3) Piping Flex Connector Steel, (TK # 1, 2, 3) Piping Single Wall Submersible (STP) Sump XERXES Fiberglass
- (d) Product to be stored in each tank: (TK # 1) Gasoline Regular, (TK # 2) Gasoline Premium, (TK # 3) Diesel Fuel
- (e) Type of leak detection being used:
 - Tank: (TK # 1, 2, 3) Leak Detect Tank Automatic Tank Gauging Veeder Root TLS 350 Business Inventory Reconciliation option, (TK # 1, 2, 3) Leak Detect Tank Interstitial Monitoring Veeder Root TLS 350
 - Piping: (TK # 1, 2, 3) Leak Detect Piping Mechanical Pressurized Line Leak Detection Vaporless 99LD-2000, (TK # 1, 2, 3) Leak Detect Piping Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 350 interstitial piping float sensor NOTE: Sensors must shut down the submersible upon detection of a leak per 175.640 a) 2)
- (f) Corrosion Protection being used:

Tank: (TK # 1, 2, 3) Corrosion Prot - Tank - Fiberglass Non-Corrosive

Piping: (TK # 1, 2, 3) Corrosion Prot - Piping - Flexible Non-Corrosive

- (g) Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3) Spill Contain Device Double Wall Spill Bucket OPW 1C-3132D Edge
- (h) Overfill prevention devices: (TK # 1, 2, 3) Overfill Prev Device Overfill Drop Tube Valve OPW 71SO-410C
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.govor by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS: There shall be a minimum of two manufactured slotted or perforated observation wells of at lease 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut

off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

(6) <u>SPECIAL CONTINGENCIES</u>: NOTE: Dispenser sumps being installed

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Anderson Pump Service, Inc. 19659 South 97th Avenue Mokena, IL 60448 Contact Person: Ronald Anderson

Phone: (708) 478-6190

Contractor Registration # IL002275 Exp. 5/21/2020

Sincerely,

Daniel Starks

Daniel J. Starke

cc: Storage Tank Safety Specialist Division File