



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 2043791
Permit # 00862-2019INS
Request Rec'd 04/29/2019
Amended Date
Approval Date 5/2/2019 DS
Permit Expires 11/4/2019

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p>(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity:</p> <p>Costco Wholesale Corporation P.O. Box 35005 Seattle, WA 98124</p> <p>Contact: Jay S.Grubb (206) 313-8100</p>	<p>(2) <u>FACILITY</u> - name and address where tanks are located:</p> <p>Costco Gasoline #348 2930 Patriot Boulevard Glenview, IL 60025</p> <p>Contact: Mike Jonscher (847) 730-1003</p>
---	--

(3) INSTALLATION OF TANKS:

(a) *Number and size of tanks being installed: (TK # 5) - 30,000*

(b) *Type of tank(s): (TK # 5) Tank - Fiberglass Brine Filled Double Wall Containment Solutions*

(c) *Type of piping: (TK # 5) Piping - Fiberglass Double Wall Ameron from remote fill to tank and from tank to 5 new dispensers. Site drawing also shows new piping from tank to connect to existing Lubrizol piping, (TK # 5) Piping - Ball Valves, (TK # 5) Piping - Shear Valves, (TK # 5) Piping - Flex Connector Steel, (TK # 5) Piping - Single Wall STP/Tanktop Sump Containment Solutions Fiberglass*

(d) *Product to be stored in each tank: (TK # 5) - Gasoline - Regular*

(e) *Type of leak detection being used:*

Tank: (TK # 5) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 350R, (TK # 5) Leak Detect - Tank - Interstitial Monitoring Veeder Root TLS 350R

Piping: (TK # 5) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 350R, (TK # 5) Leak Detect - Piping - Non-Discriminating Sump Sensor Interstitial Monitoring Veeder Root in remote fill sump, in submersible sump and in all dispenser sumps. NOTE: Sensors must shut down the submersible pump upon detection of a leak per 175.640 a) 1)

(f) *Corrosion Protection being used:*

Tank: (TK # 5) Corrosion Prot - Tank - Fiberglass Non-Corrosive

Piping: (TK # 5) Corrosion Prot - Piping - Fiberglass Non-Corrosive

(g) *Spill containment devices, piping and dispenser containment devices: (TK # 5) Spill Contain Device - Single Wall Spill Bucket OPW FibreTite Multi-port*

(h) *Overfill prevention devices: (TK # 5) Overfill Prev Device - Overfill Drop Tube Valve OPW 71SO-410C, (TK # 5) Overfill Prev Device - Overfill Alarm Veeder Root TLS 350R*

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.

(5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All

steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.


- (6) **SPECIAL CONTINGENCIES** : Installing (1) 30,000 gallon tank. Expanding canopy to install (5) new dispensers, (5) Bravo B800 Dispenser Sumps and islands. New tank will be siphoned to existing tank #2 under upgrade permit. Reusing existing Veeder Root. We will be applying for an upgrade permit for the work on existing tanks. **NOTE: Please refer to our rules pertaining to remote fills, section 175.445 e) All remote fills installed after May 1, 2003 shall be double-wall and constructed of noncorrosive material or cathodically protected, except for gravity flow waste oil.**
- f) After May 1, 2003, any new installation with a remote fill over 20 feet in length shall have interstitial monitoring and an audible and visible overfill alarm. Remote fills shall be sloped back to the tank.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Stenstrom Petroleum Services Group
2422 Center Street
Rockford, IL 61108

Contact Person: Robert Stenstrom
Phone: (815) 398-6250
Contractor Registration # IL1890 Exp. 4/12/2020

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist
Division File