



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

Amended

FOR OFFICE USE ONLY
Facility # 2-044046
Permit # 00847-2008INS
Request Rec'd 05/28/2008
Amended Date 07/22/2008
Approval Date 5/29/2008 DS
Permit Expires 11/29/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: D Construction Inc 1488 S Broadway Coal City, IL 60416 Contact: Ken Sandeno JR (815) 634-2555	(2) FACILITY - name and address where tanks are located: D Construction 2115 Moen Avenue Rockdale, Will Co., IL Contact:
---	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed:** (TK # 1, 2) - 12,000 gallons
- (b) Type of tanks:** (TK # 1, 2) - (Installing) Containment Solutions double wall fiberglass
- (c) Type of piping:** (TK # 1, 2) - (Installing) A.P.T. Poly Tech P175 SC double wall flexible
- (d) Product to be stored in each tank:** (TK # 1, 2) - Diesel Fuel
- (e) Type of leak detection being used:**
 - Tank:** (TK # 1, 2) - (Installing) Veeder Root TLS 350 Plus Interstitial tank sensor, (TK # 1, 2) - (Installing) Veeder Root TLS 350 Plus Automatic tank gauge with CSLD
 - Piping:** (TK # 1, 2) - (Installing) Veeder Root TLS 350 Plus line leak detector, (TK # 1, 2) - (Installing) Veeder Root TLS 350 Plus interstitial piping sump sensors at each submersible sump and each dispenser sump.
- (f) Corrosion Protection being used:**
 - Tank:** (TK # 1, 2) - (Installing) Fiberglass
 - Piping:** (TK # 1, 2) - (Installing) Non-corrosive flexible
- (g) Spill containment devices:**
- (h) Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.**

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u> Contact Person: Phone: (815) 265-7364 Contractor Registration # IL-1224 Exp.
--

Sincerely,

cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)