



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

FOR OFFICE USE ONLY
Facility # 5-016423
Permit # 01173-2008INS
Request Rec'd 07/16/2008
Amended Date
Approval Date 7/16/2008 JC
Permit Expires 1/16/2009

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Blessing Hospital P.O. Box 7005 Quincy, IL 62305 Contact: Mike Behrens	(2) FACILITY - name and address where tanks are located: Blessing Hospital 14th & Broadway Quincy, Adams Co., IL Contact: Mike Behrens (217) 223-1200
--	--

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed:** (TK # 6) - 2,500 gallons
- (b) Type of tanks:** (TK # 6) - (Installing) Containment Solutions double wall fiberglass brine filled
- (c) Type of piping:** (TK # 6) - Existing partial above ground single wall steel from new transition sump to building (this piping is approximately 50' long, in an open trench, and with a steel grate over the trench line), (TK # 6) - (Installing) partial - approximately 50' - A.P.T. Poly Tech P100SC double wall flexible from the tank to the new transition sump where it will hook into the existing single wall above ground steel piping.
- (d) Product to be stored in each tank:** (TK # 6) - Diesel Fuel
- (e) Type of leak detection being used:**
 - Tank:** (TK # 6) - (Installing) Veeder Root TLS 350 hydrostatic reservoir sensor, (TK # 6) - Existing automatic tank gauging console to remain. Contractor will install an ATG probe only.
 - Piping:** (TK # 6) - (Installing) European Suction
- (f) Corrosion Protection being used:**
 - Tank:** (TK # 6) - (Installing) Fiberglass
 - Piping:** (TK # 6) - (Installing) Non-corrosive flexible
- (g) Spill containment devices:**
- (h) Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.**

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u> Contact Person: Marty Jackson Phone: Contractor Registration # IL-2021 Exp. 06/25/2010
--

Sincerely,

cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)