



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

FOR OFFICE USE ONLY
Facility # 6-016407
Permit # 00912-2008INS
Request Rec'd 06/05/2008
Amended Date
Approval Date 6/5/2008 JC
Permit Expires 12/5/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Clinton County Oil Co., Inc. P. O. Box 155 Breese, IL 62230 Contact: Gene Bickl (618) 526-7570	(2) FACILITY - name and address where tanks are located: C C Food Mart 1221 12th St Carlyle, Clinton Co., IL Contact: Dale Wade (618) 526-7291
--	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed:** (TK # 6) - 15,000 gallons, (TK # 7) - 12,000 gallons, (TK # 8) - 4,000 gallons
- (b) Type of tanks:** (TK # 6, 7, 8) - (Installing) Containment Solutions double wall fiberglass
- (c) Type of piping:** (TK # 6, 7, 8) - (Installing) Ameron Dualoy 3000/LCX double wall fiberglass
- (d) Product to be stored in each tank:** (TK # 6, 8) - Gasoline, (TK # 7) - Diesel Fuel
- (e) Type of leak detection being used:**
 - Tank:** (TK # 6, 7, 8) - (Installing) Veeder Root TLS350j interstitial tank sensor, (TK # 6, 7, 8) - (Installing) Veeder Root TLS350j automatic tank gauge (Existing console and probes from the old tank system will be re-used. Also, an ILS - 350 will be installed to the ATG console system to handle the added interstitial sensor needs. Note: this system also appears to have existing CSLD from the original TLS-350j ATG installation).
 - Piping:** (TK # 6, 7, 8) - (Installing) Veeder Root TLS350j interstitial piping sump sensors at all submersible sumps and all dispenser sumps, (TK # 6, 7, 8) - (Installing) Veeder Root TLS350j electronic line leak detector
- (f) Corrosion Protection being used:**
 - Tank:** (TK # 6, 7, 8) - (Installing) Fiberglass
 - Piping:** (TK # 6, 7, 8) - (Installing) Fiberglass
- (g) Spill containment devices:**
- (h) Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.**

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u> Contact Person: Harvey Stokes Phone: Contractor Registration # IL-246 Exp. 05/28/2010
--

Sincerely,