



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL  
Division of Technical Services  
1035 Stevenson Drive  
Springfield, Illinois 62703-4259  
(217)524-7605

FOR OFFICE USE ONLY  
Facility # 4-044037  
Permit # 00764-2008INS  
Request Rec'd 05/13/2008  
Amended Date  
Approval Date 5/13/2008 JC  
Permit Expires 11/13/2008

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>(1) OWNER OF TANKS</b> - Corporation, partnership, or other business entity:  Area Disposal Clinton Route 51 South, RR #2 Box 216L Clinton, IL 61727  Contact:	<b>(2) FACILITY</b> - name and address where tanks are located:  Area Disposal Clinton Route 51 South, RR #2 Box 216L Clinton, Dewitt Co., IL  Contact:
---	---

**(3) INSTALLATION OF TANKS:**

- (a) Number and size of tanks being installed:** (TK # 1) - 20,000 gallons
- (b) Type of tanks:** (TK # 1) - (Installing) Glasteel II double wall composite
- (c) Type of piping:** (TK # 1) - (Installing) Ameron Dualoy 3000/LCX double wall fiberglass
- (d) Product to be stored in each tank:** (TK # 1) - Diesel Fuel
- (e) Type of leak detection being used:**
  - Tank:** (TK # 1) - (Installing) Veeder Root TLS 350 interstitial tank sensor, (TK # 1) - (Installing) Veeder Root TLS350 automatic tank gauge
  - Piping:** (TK # 1) - (Installing) Veeder Root TLS350 interstitial piping sump sensors at submersible sump and at dispenser sump, (TK # 1) - (Installing) Red Jacket FX1DV mechanical line leak detector
- (f) Corrosion Protection being used:**
  - Tank:** (TK # 1) - (Installing) Composite
  - Piping:** (TK # 1) - (Installing) Fiberglass
- (g) Spill containment devices:**
- (h) Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at [www.state.il.us/osfm](http://www.state.il.us/osfm) or by calling (217)785-1020.**

**(5) GENERAL REQUIREMENTS:**

**(6) SPECIAL CONTINGENCIES:**

<b>(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u></b>          Contact Person: Phone: (309) 347-1819  Contractor Registration # IL-1293 Exp.
--

Sincerely,

cc: Storage Tank Safety Specialist -  
Fire Department -  
Office Coordinator -  
Division File  
(Rev. - 1/98)