



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

Extended

FOR OFFICE USE ONLY
Facility # 2-043851
Permit # 01805-2007INS
Request Rec'd 10/30/2007
Amended Date
Approval Date 10/31/2007 JC
Permit Expires 10/30/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Emmanuel Joseph 1448 Executive Lane Glenview, IL 60026 Contact:	(2) FACILITY - name and address where tanks are located: Kerolite Oil 9660 Golf Rd. Des Plaines, Cook Co., IL Contact:
---	---

(3) INSTALLATION OF TANKS:

- (a) **Number and size of tanks being installed:** (TK # 1) - 15,000 gallons, (TK # 2) - 6,000 gallons, (TK # 3) - 10,000 gallons
- (b) **Type of tanks:** (TK # 1, 2, 3) - (Installing) Containment Solutions double wall fiberglass
- (c) **Type of piping:** (TK # 1, 2, 3) - (Installing) A.O. Smith double wall fiberglass
- (d) **Product to be stored in each tank:** (TK # 1, 2) - Gasoline, (TK # 3) - Diesel Fuel
- (e) **Type of leak detection being used:**
Tank: (TK # 1, 2, 3) - (Installing) Veeder Root TLS 350 with CSLD automatic tank gauge, (TK # 1, 2, 3) - (Installing) Veeder Root TLS 350 interstitial tank sensor
Piping: (TK # 1, 2, 3) - (Installing) Veeder Root TLS350 interstitial piping sump sensors at all submersible sumps and at all dispenser sumps, (TK # 1, 2, 3) - (Installing) Veeder Root TLS350 electronic line leak detector
- (f) **Corrosion Protection being used:**
Tank: (TK # 1, 2, 3) - (Installing) Fiberglass
Piping: (TK # 1, 2, 3) - (Installing) Fiberglass
- (g) **Spill containment devices:**
- (h) **Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u> Contact Person: Kevin Krohn Phone: Contractor Registration # IL-1175 Exp. 03/04/2008
--

Sincerely,

cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)