



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

FOR OFFICE USE ONLY
Facility # 1-044024
Permit # 00658-2008INS
Request Rec'd 04/29/2008
Amended Date
Approval Date 5/1/2008 JC
Permit Expires 11/1/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Con-Way Freight, Inc. 110 Parkland Plaza Ann Arbor, MI 48103 Contact: Jeff Sexten	(2) FACILITY - name and address where tanks are located: ConWay Service Center 750 Progress Parkway La Salle, LaSalle Co., IL Contact:
---	---

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed:** (TK # 1, 2, 3) - 20,000 gallons, (TK # 4) - 12,000 gallons, (TK # 5) - 2,500 gallons
- (b) Type of tanks:** (TK # 1, 2, 3, 4, 5) - (Installing) XERXES double wall fiberglass
- (c) Type of piping:** (TK # 1, 2, 3, 4, 5) - (Installing) A.O. Smith double wall fiberglass to also include a siphon bar between tank #2 & #3.
- (d) Product to be stored in each tank:** (TK # 1, 2, 3) - Diesel Fuel, (TK # 4) - Motor Oil, (TK # 5) - Used Oil
- (e) Type of leak detection being used:**
 - Tank:** (TK # 1, 2, 3, 4, 5) - (Installing) Veeder Root TLS 350 with CSLD automatic tank gauge, (TK # 1, 2, 3, 4, 5) - (Installing) Veeder Root TLS 350 interstitial tank sensor
 - Piping:** (TK # 1, 2) - (Installing) Veeder Root TLS350 electronic line leak detector, (TK # 1, 2, 3) - (Installing) Veeder Root TLS350 interstitial piping sump sensors at all dispenser sumps, submersible sumps, remote fill sumps, and for both ends of the siphon bar at tank #2 & #3, (TK # 4) - (Installing) European Suction, (TK # 5) - (Installing) Gravity feed and less than 25 gallon fills.
- (f) Corrosion Protection being used:**
 - Tank:** (TK # 1, 2, 3, 4, 5) - (Installing) Fiberglass
 - Piping:** (TK # 1, 2, 3, 4, 5) - (Installing) Fiberglass
- (g) Spill containment devices:**
- (h) Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.**

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u> Contact Person: Nate Meyer Phone: Contractor Registration # IL-1890 Exp. 03/07/2010

Sincerely,

