



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

FOR OFFICE USE ONLY

Facility # 1046862
Permit # 01029-2019INS
Request Rec'd 05/20/2019
Amended Date
Approval Date 5/30/2019 DS
Permit Expires 12/3/2019

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity: Meijer Great Lakes Limited Partnership 2929 Walker Avenue, NW Grand Rapids, MI 495449428 Contact: Erik Petrovoskis (616) 453-6711	(2) <u>FACILITY</u> - name and address where tanks are located: Meijer Gas #313 601 Peace Road Sycamore, IL 60178 Contact: David Gilmore (616) 791-3747
---	---

(3) INSTALLATION OF TANKS:

- (a) *Number and size of tanks being installed: (TK # 1) - 20,000, (TK # 2, 4) - 8,000, (TK # 3) - 10,000*
- (b) *Type of tank(s): (TK # 1, 2, 3, 4) Tank - Fiberglass Double Wall XERXES*
- (c) *Type of piping: (TK # 1, 2, 3, 4) Piping - Fiberglass Double Wall NOV Fiberglass Systems Red Thread IIA fiberglass piping from tanks to dispensers as shown in site plan, (TK # 1, 2, 3, 4) Piping - Ball Valves, (TK # 1, 2, 3, 4) Piping - Positive Shutoff Valves, (TK # 1, 2, 3, 4) Piping - Shear Valves, (TK # 1, 2, 3, 4) Piping - Single Wall STP/Tanktop Sump XERXES Fiberglass*
- (d) *Product to be stored in each tank: (TK # 1) - Gasoline - Regular, (TK # 2) - Gasoline - Premium, (TK # 3) - Diesel Fuel, (TK # 4) - E-85*
- (e) *Type of leak detection being used:*
- Tank: (TK # 1, 2, 3, 4) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 450 Plus, (TK # 1, 2, 3, 4) Leak Detect - Tank - Hydrostatic Reservoir Sensors Interstitial Monitoring Veeder Root TLS 450 Plus Interstitial tank sensor*
- Piping: (TK # 1, 2, 3, 4) Leak Detect - Piping - Electronic Pressurized Line Leak Detection Veeder Root TLS 450 Plus 8590 DPLLD, (TK # 1, 2, 3, 4) Leak Detect - Piping - Non-Discriminating Sump Sensor Interstitial Monitoring Veeder Root in all submersible and dispenser sumps. NOTE: Sensors must shut down the submersible pump supplying that line upon detection of a leak per 175.640 a) 1)*
- (f) *Corrosion Protection being used:*
- Tank: (TK # 1, 2, 3, 4) Corrosion Prot - Tank - Fiberglass Non-Corrosive*
- Piping: (TK # 1, 2, 3, 4) Corrosion Prot - Piping - Fiberglass Non-Corrosive*
- (g) *Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3) Spill Contain Device - Double Wall Spill Bucket Emco Wheaton A1004, (TK # 4) Spill Contain Device - Single Wall Spill Bucket OPW 1C-2100-DEVR*
- (h) *Overfill prevention devices: (TK # 1, 2, 3) Overfill Prev Device - Overfill Drop Tube Valve OPW 7ISO-410C, (TK # 1, 2, 3, 4) Overfill Prev Device - Overfill Alarm Veeder Root TLS 450plus, (TK # 4) Overfill Prev Device - Overfill Drop Tube Valve OPW 7ISOM*
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov by calling (217)785-1020.
- (5) **GENERAL REQUIREMENTS** : There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight

containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.


- (6) **SPECIAL CONTINGENCIES** : NOTE: Dispenser setbacks from building and property lines are met. Compatibility checklist and associated documentation for tank #4 included in application

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Crowne Industries, Ltd.
651 S. Sutton Road #214
Streamwood, IL 60107

Contact Person: Robert Sumoski
Phone: (630) 497-9009
Contractor Registration # IL002345 Exp. 5/16/2020

Sincerely,



Daniel Starks

cc: Storage Tank Safety Specialist
Division File