



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

FOR OFFICE USE ONLY
Facility # 2-023693
Permit # 00098-2008INS
Request Rec'd 01/15/2008
Amended Date
Approval Date 1/16/2008 JC
Permit Expires 7/16/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) OWNER OF TANKS - Corporation, partnership, or other business entity: Morris Hospital 150 W High St Morris, IL 60450 Contact: Perdue Dennis (815) 942-2932	(2) FACILITY - name and address where tanks are located: Morris Hospital 150 W High St Morris, Grundy Co., IL Contact: Perdue Dennis (815) 942-2932
--	--

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed:** (TK # 4) - 20,000 gallons
- (b) Type of tanks:** (TK # 4) - (Installing) XERXES double wall fiberglass
- (c) Type of piping:** (TK # 4) - (Installing) A.P.T. Poly Tech P150SC double wall flexible piping consisting of: (2) - supply lines and (1) - return line.
- (d) Product to be stored in each tank:** (TK # 4) - Diesel Fuel
- (e) Type of leak detection being used:**
 - Tank:** (TK # 4) - (Installing) Veeder Root TLS 300 automatic tank gauge, (TK # 4) - (Installing) Veeder Root TLS 300 Interstitial tank sensor
 - Piping:** (TK # 4) - (Installing) Veeder Root TLS 300 interstitial piping sump sensor at the tank sump, (TK # 4) - (Installing) European Suction
- (f) Corrosion Protection being used:**
 - Tank:** (TK # 4) - (Installing) Fiberglass
 - Piping:** (TK # 4) - (Installing) Non-corrosive flexible
- (g) Spill containment devices:**
- (h) Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.**

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u> Contact Person: Robert Sumoski Phone: 630-497-9009 Contractor Registration # IL-002345 Exp.

Sincerely,

cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)