

## OFFICE OF THE ILLINOIS STATE FIRE MARSHAL Division of Technical Services

1035 Stevenson Drive Springfield, Illinois 62703-4259 (217)524-7605

## FOR OFFICE USE ONLY

Facility # 3-043875
Permit # 01929-2007INS
Request Rec'd 11/16/2007
Amended Date
Approval Date 11/19/2007 JC
Permit Expires 5/19/2008

## Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE**.

(1) OWNER OF TANKS - Corporation, partnership, or other business entity:	(2) <u>FACILITY</u> - name and address where tanks are located:
Air Land Transport Ser Inc Po Box 968 Morton, IL 61550	Air-Land Transport Service, Inc. 17508 Route 5 & 92 East Moline, Rock Island Co., IL
Contact: Paccotti John (309) 673-1227	Contact:

## (3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 1) 12,000 gallons
- (b) Type of tanks: (TK # 1) (Installing) Glasteel II double wall composite
- (c) Type of piping: (TK # 1) (Installing) A.P.T. Poly Tech P175 SC double wall flexible
- (d) Product to be stored in each tank: (TK # 1) Diesel Fuel
- (e) Type of leak detection being used:

*Tank:* (TK # 1) - (Installing) Veeder Root TLS 300c interstitial tank sensor, (TK # 1) - (Installing) Veeder Root TLS300c with CSLD automatic tank gauge

**Piping:** (TK # 1) - (Installing) Veeder Root TLS300c interstitial piping sump sensor at submersible sump and both dispenser sumps, (TK # 1) - (Installing) FE Petro STP-MLD-D mechanical line leak detector

(f) Corrosion Protection being used:

Tank: (TK # 1) - (Installing) Composite

**Piping:** (TK # 1) - (Installing) Non-corrosive flexible

- (g) Spill containment devices:
- (h) Overfill prevention devices:
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at <a href="https://www.state.il.us/osfm">www.state.il.us/osfm</a> or by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS:
- (6) **SPECIAL CONTINGENCIES**:

(7)	PERSON.	FIRM OR	<b>COMPANY</b>	PERFORMING	WORK:
-----	---------	---------	----------------	------------	-------

Contact Person:

Phone: 515-261-7721

Contractor Registration # IL-598 Exp.

Sincerely,

cc: Storage Tank Safety Specialist -

Fire Department -

Office Coordinator -

Division File

(Rev. - 1/98)

James of Coffey