

Office of the Illinois State Fire Marshal Division of Petroleum and Chemical Safety

1035 Stevenson Drive Springfield, IL 62703 2177851020

FOR OFFICE USE ONLY

Facility # 2047046 Permit # 00640-2020INS Request Rec'd 04/27/2020 Amended Date Approval Date 5/4/2020 DS Permit Expires 11/5/2020

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business

entity:

True North Energy, LLC 10346 Brecksville Road Brecksville, OH 44141

Contact: Mahboob Abbas (877) 245-9336

(2) FACILITY - name and address where tanks are located:

True North Energy LLC 1 Green Bay Road Waukegan, IL 60085

Contact: David Nye (877) 245-9336

(3) <u>INSTALLATION OF TANKS:</u>

- (a) Number and size of tanks being installed: (TK # 1) 15,000, (TK # 2, 3, 5) 6,000, (TK # 4) 9,000
- (b) Type of tank(s): (TK # 1, 2, 3, 4, 5) Tank Fiberglass Double Wall Containment Solutions
- (c) Type of piping: (TK # 1, 2, 3, 4, 5) Piping Flexible Double Wall Franklin Fueling Systems UPP from tanks to dispensers as shown in drawing, (TK # 1, 2, 3, 4, 5) Piping Single Wall STP/Tanktop Sump
- (d) Product to be stored in each tank: (TK # 1, 2) Gasoline Regular, (TK # 3) Gasoline Premium, (TK # 4) Diesel Fuel, (TK # 5) E-15
- (e) Type of leak detection being used:

Tank: (TK # 1, 2, 3, 4, 5) Leak Detect - Tank - Automatic Tank Gauging Veeder Root TLS 450 Plus with CSLD, (TK # 1, 2, 3, 4, 5) Leak Detect - Tank - Non-Discriminating Sensors Interstitial Monitoring

Piping: (TK # 1, 2, 3, 4, 5) Leak Detect - Piping - Electronic Pressurized Line Leak Detection, (TK # 1, 2, 3, 4, 5) Leak Detect - Piping - Non-Discriminating Sump Sensor with positive shutdown in all submersible and dispenser sumps

(f) Corrosion Protection being used:

Tank: (TK # 1, 2, 3, 4, 5) Corrosion Prot - Tank - Fiberglass Non-Corrosive

Piping: (TK # 1, 2, 3, 4, 5) Corrosion Prot - Piping - Flexible Non-Corrosive

- (g) Spill containment devices, piping and dispenser containment devices: (TK # 1, 2, 3, 4, 5) Spill Contain Device Single Wall Spill Bucket
- (h) Overfill prevention devices: (TK # 1, 2, 3, 4, 5) Overfill Prev Device Overfill Drop Tube Valve
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.govor by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS: There shall be a minimum of two manufactured slotted or perforated observation wells of at lease 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion

protection.

(6) SPECIAL CONTINGENCIES:

Installing (1) 15,000 gallon, (1) 15,000 gallon (split 9&6), and (1) 12,000 gallon (split 6&6) Containment Solutions double wall fiberglass tanks. New

tank sumps and dispenser sumps. UPP double wall product piping to (10) fuel islands. (2) islands will have diesel fuel and (8) islands will have E15. Vent pipe to be UPP single wall. New Veeder Root TLS 450 Plus with mag plus probes, sump sensors, interstitial sensors, and plld's.

NOTE: Application and drawing show the tank field doesn't meet the 20' setback requirement, however, since tanks and piping are double wall with interstitial monitoring the 20' isn't required as long as the entire UST system is on the property and nothing from the adjacent property will project a load onto the tanks being installed.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Metro Environmental Contractors, Inc. dba Metro Tank & Pump

Company

1111 West Dundee Road

Wheeling, IL 600903936

Contact Person: Warren Cherner

Phone: (847) 465-4000

Contractor Registration # IL102 Exp. 2/7/2022

Sincerely,

Daniel Starks

Daniel J. Starke

cc: Storage Tank Safety Specialist Division File