



Office of the Illinois State Fire Marshal
Division of Petroleum and Chemical Safety
1035 Stevenson Drive
Springfield, IL 62703
2177851020

Amended

FOR OFFICE USE ONLY

Facility # 1028432
Permit # 00473-2020UPG
Request Rec'd 03/20/2020
Amended Date 05/06/2020 DS
Approval Date 3/23/2020 DS
Permit Expires 9/23/2020

Permit for UPGRADE or REPAIR of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to upgrade or repair underground storage tank(s) or piping is hereby granted. Such upgrade or repair must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for underground piping upgrade, leak detection, spill and overfill prevention of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety.

<p>(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity:</p> <p>Beck Oil Company of Illinois 850 E. Thompson St. Princeton, IL 61356</p> <p>Contact: Gerri Frank (815) 315-0265</p>	<p>(2) <u>FACILITY</u> - name and address where tanks are located:</p> <p>Beck's #27 1302 Raymond Drive Mendota, IL 61342</p> <p>Contact: Kevin Gerard (815) 539-3300</p>
------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

(3) UPGRADE OR REPAIR OF TANKS:

(a) Number and size of tanks being upgraded or repaired: (TK # 2, 3) - 12,000

(b) Type of tanks:

(c) Type of piping: (TK # 2, 3) Piping - Flexible Double Wall A.P.T. Poly Tech P150SC from existing tanks to transition sump at the blending shed, (TK # 2, 3) Piping - Flexible Double Wall A.P.T. Poly Tech P200SC from blending shed to dispensers, (TK # 2, 3) Piping - Single Wall Transition Sump

(d) Product to be stored in each tank: (TK # 2, 3) - B-11

(e) Type of leak detection being used:

Tank:

Piping: (TK # 2, 3) Leak Detect - Piping - Electronic Pressurized Line Leak Detection, (TK # 2, 3) Leak Detect - Piping - Non-Discriminating Sump Sensor in all submersible, transition and dispenser sumps.

NOTE: Sensors must wired for positive shut down

(f) Corrosion Protection being used:

Tank:

Piping:

(g) Spill containment devices, piping, and dispenser containmnt devices: (TK # 2, 3) Spill Contain Device - Double Wall Spill Bucket

(h) Overfill prevention devices: (TK # 2, 3) Overfill Prev Device - Overfill Drop Tube Valve

(i) Manway accessible at grade:

(4) The owner must notify this Office when completion of tank upgrade/repair has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for underground piping upgrade, leak detection, spill and overfill prevention to the OSFM prior to the work being performed. Both forms can be obtained at www.sfm.illinois.gov or by calling (217)785-1020.

(5) SPECIAL CONTINGENCIES :

We are repiping all Diesel lines from existing tanks to blending shed. At the blending shed there will be 2 transitin sumps where we would go from Fiberglass pipe to the APT 2" double wall pipe. This will be ran to the Dispensers then the Satalite lines to slaves will be APT 1 1/2" APT double wall. We will be installing new tank sumps on Diesel tanks with new Submersibles and 2-Incon EVO electronic line leak detectors

that will tie into the Existing EVO-550 ATG. ALL transition sumps and dispenser sumps will get Incon -ULS sump sensors.


Amendment Reason: We installed a Incon TS550 and it will not test the amount of pipe that we installed in the ground. { The runs are to long
} We intalled a Incon TS550 and it will not test the amount of pipe that we put in the ground. The leangh of pipe is to long on the Diesel side.
So we would like to change it out to a Veeder Root 450 Plus.

(6) PERSON, FIRM OR COMPANY PERFORMING WORK:

Pipeco, Inc.
610 29TH ST
Bettendorf, IA 52722

Contact Person: Debbie Rindler
Phone: (563) 344-0700
Contractor Registration # IL2034 Exp. 9/28/2020

Sincerely,

A handwritten signature in cursive script that reads "Daniel S. Starks". The signature is written in dark ink and is positioned above a horizontal line.

Daniel Starks

cc: Storage Tank Safety Specialist
Division File