OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

FOR OFFICE USE ONLY
Facility # 2-010030
Permit # 01881-2007INS
Request Rec'd 11/08/2007
Amended Date
Approval Date 11/13/2007 JC
Permit Expires 5/13/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE**.

(1) OWNER OF TANKS - Corporation, partnership, or other business entity:	**(2) FACILITY** - name and address where tanks are located:
Khalid Jim Siddiqui 1823 W. Hood Ave. Suite C. Chicago, IL 60660 Contact: Khalil Siddiqui (773) 406-7777	Clark 926 N. York Road Elmhurst, Du Page Co., IL Contact: Khalid Siddiqui (773) 406-7777

(3) INSTALLATION OF TANKS:

(a) Number and size of tanks being installed: One compartment tank consisting of: (TK # 7) - 8,000 gallons, (TK # 8) - 4,000 gallons

(b) Type of tanks: (TK # 7, 8) - (Installing) XERXES double wall fiberglass brine filled

(c) Type of piping: (TK # 7, 8) - (Installing) Ameron Dualoy 3000/LCX double wall fiberglass

(d) Product to be stored in each tank: (TK # 7) - Gasoline, (TK # 8) - Diesel Fuel

(e) Type of leak detection being used:

Tank: (TK # 7, 8) - (Installing) Veeder Root TLS350 automatic tank gauge, (TK # 7, 8) - (Installing) Veeder Root TLS 350 hydrostatic reservoir sensor

Piping: (TK # 7, 8) - (Installing) Veeder Root TLS350 interstitial piping sump sensors at both submersible sumps, and at the northernmost dispenser sump only (the one that is 16' from the property line), (TK # 7, 8) - (Installing) Veeder Root TLS350 electronic line leak detector

(f) Corrosion Protection being used:

Tank: (TK # 7, 8) - (Installing) Fiberglass

Piping: (TK # 7, 8) - (Installing) Fiberglass

(g) Spill containment devices:

(h) Overfill prevention devices:

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) PERSON, FIRM OR COMPANY PERFORMING WORK:

Contact Person:
Phone:

Contractor Registration # IL-002329 Exp.

Sincerely,

James J. Coffey

cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)