



**OFFICE OF THE ILLINOIS STATE FIRE MARSHAL**  
**Division of Technical Services**  
 1035 Stevenson Drive  
 Springfield, Illinois 62703-4259  
 (217)524-7605

<b>FOR OFFICE USE ONLY</b>
Facility # 6-021339
Permit # 01754-2007INS
Request Rec'd 10/22/2007
Amended Date
Approval Date 10/24/2007 JC
Permit Expires 4/24/2008

**Permit for Installation of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for underground piping upgrade, leak detection, spill and overfill prevention of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p><b>(1) OWNER OF TANKS</b> - Corporation, partnership, or other business entity:          Yogibapa, LLC          411 N. Main          Caseyville, IL 62232          Contact:</p>	<p><b>(2) FACILITY</b> - name and address where tanks are located:          Han-Dee Mart          411 N. Main          Caseyville, St. Clair Co., IL          Contact: Prince Patel (618) 398-6745</p>
--	--

**(3) Installation OF TANKS:**

- (a) **Number and size of tanks being upgraded or repaired:** (TK # 3) - 15,000 gallons, (TK # 4, 6) - 6,000 gallons, (TK # 5) - 10,000 gallons
- (b) **Type of tanks:** (TK # 3, 4, 5, 6) - (Installing) XERXES single wall fiberglass
- (c) **Type of piping:** (TK # 3, 4, 5, 6) - (Installing) Ameron Dualoy 3000/LCX double wall fiberglass
- (d) **Product to be stored in each tank:** (TK # 3, 5) - Gasoline, (TK # 4) - Diesel Fuel, (TK # 6) - E-85
- (e) **Type of leak detection being used:**  
  - Tank:** (TK # 3, 4, 5, 6) - (Installing) Veeder Root TLS 350 Plus Automatic tank gauge probes will be installed only. The existing console that was being used for tanks 1 & 2 will be re-used for these new tanks.
  - Piping:** (TK # 3, 4, 5, 6) - (Installing) Veeder Root TLS 350 Plus line leak detector
- (f) **Corrosion Protection being used:**  
  - Tank:** (TK # 3, 4, 5, 6) - (Installing) Fiberglass
  - Piping:** (TK # 3, 4, 5, 6) - (Installing) Fiberglass
- (g) **Spill containment devices:** (TK # 3, 4, 5, 6) - (Installing) OPW 1-2100 spill containment manhole
- (h) **Overfill prevention devices:**
- (i) **Manway accessible at grade:**

**(4) The owner must notify this Office when completion of tank upgrade/repair has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for underground piping upgrade, leak detection, spill and overfill prevention to the OSFM prior to the work being performed. Both forms can be obtained at [www.state.il.us/osfm](http://www.state.il.us/osfm) or by calling (217)785-1020.**

**(5) SPECIAL CONTINGENCIES:**

<p><b>(6) PERSON, FIRM OR COMPANY PERFORMING WORK:</b></p> <p align="right">Contact Person: Rick Durbin          Phone:          Contractor Registration # Exp. 02/10/2008</p>
--

Sincerely,

*James J. Coffey*