

## OFFICE OF THE ILLINOIS STATE FIRE MARSHAL Division of Technical Services

1035 Stevenson Drive Springfield, Illinois 62703-4259 (217)524-7605

## FOR OFFICE USE ONLY

Facility # 4-009648
Permit # 01746-2007INS
Request Rec'd 10/18/2007
Amended Date
Approval Date 10/23/2007 JC
Permit Expires 4/23/2008

## Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE**.

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity:	(2) <u>FACILITY</u> - name and address where tanks are located:
Freedom Oil Company 814 W. Chestnut Street, P.O. Box 3697 Bloomington, IL 61702-3697	Freedom Oil Co. 1802 W. Market Street Bloomington, McLean Co., IL
Contact: Gene Adams (309) 828-7750	Contact: Dan (309) 828-4223

## (3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: One compartment tank consisting of: (TK # 6) 8,000 gallons, (TK # 7) 12,000 gallons
- (b) Type of tanks: (TK # 6, 7) (Installing) XERXES double wall fiberglass
- (c) Type of piping: (TK # 6, 7) (Installing) partial Ameron Dualoy 3000/LCX double wall fiberglass from the tanks to the edge of the tank field, (TK # 6, 7) Existing partial double wall fiberglass from the dispensers to the edge of the tank field (piping from the tank system that is being removed see latest removal permit).
- (d) Product to be stored in each tank: (TK # 6, 7) Gasoline
- (e) Type of leak detection being used:
  - *Tank:* (TK # 6, 7) (Installing) Veeder Root TLS350 automatic tank gauge, (TK # 6, 7) (Installing) Veeder Root TLS 350 interstitial tank sensor
  - *Piping:* (TK # 6, 7) (Installing) Veeder Root TLS350 electronic line leak detector, (TK # 6, 7) (Installing) Veeder Root TLS350 interstitial piping sump sensors at each submersible sump only.
- (f) Corrosion Protection being used:

**Tank:** (TK # 6, 7) - (Installing) Fiberglass

**Piping:** (TK # 6, 7) - Existing fiberglass, (TK # 6, 7) - (Installing) Fiberglass

- (g) Spill containment devices:
- (h) Overfill prevention devices:
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at <a href="https://www.state.il.us/osfm">www.state.il.us/osfm</a> or by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS:
- (6) SPECIAL CONTINGENCIES:

(7) PERSON, FIRM OR COMPANY PERFORMING WORK:		
	Contact Person: Phone:	
	Contractor Registration # IL-1293	Exp.

Sincerely,

James of Coffey