



**OFFICE OF THE ILLINOIS STATE FIRE MARSHAL**  
**Division of Technical Services**  
 1035 Stevenson Drive  
 Springfield, Illinois 62703-4259  
 (217)524-7605

<u>FOR OFFICE USE ONLY</u>
Facility # 1-043847
Permit # 01745-2007INS
Request Rec'd 10/22/2007
Amended Date
Approval Date 10/23/2007 JC
Permit Expires 4/23/2008

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p><b>(1) OWNER OF TANKS</b> - Corporation, partnership, or other business entity:</p> <p>Dayton Freight Lines, Inc.          6450 Poe Ave., Suite 311          Dayton, OH 45414</p> <p>Contact: Dave East (937) 235-1959</p>	<p><b>(2) FACILITY</b> - name and address where tanks are located:</p> <p>Dayton Freight Lines, Inc.          3465 American Road          Rockford, Winnebago Co., IL</p> <p>Contact:</p>
---	---

**(3) INSTALLATION OF TANKS:**

- (a) **Number and size of tanks being installed:** (TK # 1, 2) - 15,000 gallons
- (b) **Type of tanks:** (TK # 1, 2) - (Installing) Containment Solutions single wall fiberglass
- (c) **Type of piping:** (TK # 1, 2) - (Installing) Ameron Dualoy 3000/LCX double wall fiberglass
- (d) **Product to be stored in each tank:** (TK # 1, 2) - Diesel Fuel
- (e) **Type of leak detection being used:**
  - Tank:** (TK # 1, 2) - (Installing) Veeder Root TLS350 automatic tank gauge
  - Piping:** (TK # 1, 2) - (Installing) Red Jacket FX1DV mechanical line leak detector, (TK # 1, 2) - (Installing) Veeder Root TLS350 interstitial piping sump sensors at each submersible sump and each dispenser sump.
- (f) **Corrosion Protection being used:**
  - Tank:** (TK # 1, 2) - (Installing) Fiberglass
  - Piping:** (TK # 1, 2) - (Installing) Fiberglass
- (g) **Spill containment devices:**
- (h) **Overfill prevention devices:**

**(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at [www.state.il.us/osfm](http://www.state.il.us/osfm) or by calling (217)785-1020.**

**(5) GENERAL REQUIREMENTS:**

**(6) SPECIAL CONTINGENCIES:**

<p><b>(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u></b></p>	<p>Contact Person:</p> <p>Phone:</p> <p>Contractor Registration # IL-1293 Exp.</p>
---	--

Sincerely,

cc: Storage Tank Safety Specialist -  
 Fire Department -  
 Office Coordinator -  
 Division File  
 (Rev. - 1/98)