

OFFICE OF THE ILLINOIS STATE FIRE MARSHAL Division of Technical Services

1035 Stevenson Drive Springfield, Illinois 62703-4259 (217)524-7605

FOR OFFICE USE ONLY

Facility # 4-043661 Permit # 01679-2007INS Request Rec'd 10/09/2007 Amended Date Approval Date 10/15/2007 DS Permit Expires 4/15/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE**.

(1) <u>OWNER OF TANKS</u> - Corporation, partnership, or other business entity:	(2) <u>FACILITY</u> - name and address where tanks are located:
Love's Travel Stops & Country Stores Inc P.O. Box 26210 Oklahoma City, OK 73126	Love's Travel Stop #367 505 South Persimmon Drive Le Roy, McLean Co., IL
Contact: Michael Key (405) 302-6640	Contact:

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: (TK # 1, 4, 5, 6, 7) 20,000 gallons, (TK # 2) 12,000 gallons, (TK # 3) 8,000 gallons
- (b) Type of tanks: (TK # 1, 2, 3, 4, 5, 6, 7) (Installing) Glasteel II double wall composite
- (c) Type of piping: (TK # 1, 2, 3, 4, 5, 6, 7) (Installing) Ameron double wall fiberglass (see contingencies for siphon piping information)
- (d) Product to be stored in each tank: (TK # 1, 2, 3) Gasoline, (TK # 4, 5, 6) Diesel Fuel, (TK # 7) Soy Oil
- (e) Type of leak detection being used:

Tank: (TK # 1, 2, 3, 4, 5, 6, 7) - (Installing) Veeder Root TLS 350 interstitial tank sensor, (TK # 1, 2, 3, 4, 5, 6, 7) - (Installing) Veeder Root TLS 350 with CSLD automatic tank gauge

Piping: (TK # 1, 2, 3, 4, 5, 6, 7) - (Installing) Veeder Root TLS350 electronic line leak detector, (TK # 1, 2, 3, 4, 5, 6, 7) - (Installing) Veeder Root TLS350 interstitial piping sump sensors at ALL sumps (see contingencies)

(f) Corrosion Protection being used:

Tank: (TK # 1, 2, 3, 4, 5, 6, 7) - (Installing) Composite **Piping:** (TK # 1, 2, 3, 4, 5, 6, 7) - (Installing) Fiberglass

- (g) Spill containment devices:
- (h) Overfill prevention devices:
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.
- (5) **GENERAL REQUIREMENTS:**
- (6) **SPECIAL CONTINGENCIES**:

(7) PERSON, FIRM OR COMPANY PERFORMING WORK:		
	Contact Person: Phone:	
	Contractor Registration # IL-1293	Exp.

Sincerely,

Daniel J. Starks