



Office of the Illinois State Fire Marshal
 Division of Petroleum and Chemical Safety
 1035 Stevenson Drive
 Springfield, IL 62703
 2177851020

Extended

FOR OFFICE USE ONLY
 Facility # 1015668
 Permit # 01452-2020REM
 Request Rec'd 10/09/2020
 Amended Date
 Approval Date 10/13/2020 DS
 Permit Expires 10/13/2021

Permit for REMOVAL of Underground Storage Piping for Petroleum and Hazardous Substances.

Permission to remove underground storage tank piping is hereby granted. Such removal shall not commence until the contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall establish a date certain to perform the UST activity by contacting the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety, at which time the UST activity shall be scheduled. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<p>(1) OWNER OF TANKS - Corporation, partnership, or other business entity:</p> <p>Johnson Oil Company 1305 12th Avenue Rock Falls, IL 61071 Contact: Kathy Peugh (815) 625-6380</p>	<p>(2) FACILITY - name and address where tanks are located:</p> <p>Express Lane Shell 342 North Mason Amboy, IL 61310 Contact: Tabitha Berogan (815) 625-6380</p>
--	---

(3) REMOVAL OF PIPING:

- (a) Description/location of piping being removed:*
- (b) Which tank(s) are associated with the piping being removed: (TK # 6) - 4,000, (TK # 7) - 12,000*
- (c) Reason of piping being removed:*
- (d) If piping is leaking, indicate IEMA incident number:*

(4) After removal is completed, the owner/operator shall perform a site assessment by measuring for the presence of a release where contamination is most likely to be present at the UST site. This is in accordance with the Illinois Administrative Code 176.360 (a) regulations and 40 CFR Part 280.72 (a) Federal Register Requirement.

(5) SPECIAL CONTINGENCIES :

We are planning to remove the existing single wall fiberglass piping From beneath the canopy area back to an existing transition sump. After the safe removal of the old fuel lines and appropriate soil sampling from below the dispensers and lines throughout the trench, the existing canopy will be taken down and removed. New Canopy system to be installed. We will be installing new APT 2" flexible piping and sumps for secondary containment. There will be a total of 3 dispenser sumps installed and roughly 260' of piping

<p>(6) PERSON, FIRM OR COMPANY PERFORMING WORK:</p>	
<p>Illowa Enterprises, Inc. 2703 4th Avenue Moline, IL 61265</p>	<p>Contact Person: JC Cline Phone: (309) 762-1729 Contractor Registration # IL981 Exp. 5/1/2022</p>

Sincerely,

Daniel Starks

cc: Storage Tank Safety Specialist
 Division File