

OFFICE OF THE ILLINOIS STATE FIRE MARSHAL Division of Technical Services

1035 Stevenson Drive Springfield, Illinois 62703-4259 (217)524-7605

FOR OFFICE USE ONLY

Facility # 4-041236
Permit # 01512-2007INS
Request Rec'd 09/17/2007
Amended Date
Approval Date 9/19/2007 JC
Permit Expires 3/19/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE**.

(1) OWNER OF TANKS - Corporation, partnership, or other business entity:	(2) <u>FACILITY</u> - name and address where tanks are located:
Tri Star Marketing, Inc. 1301 E. Washington Street, P.O. Box 17280 Urbana, IL 61803-7280	Super Pantry #51 3810 E. William Street Decatur, Macon Co., IL
Contact: Kathy DelSignore (217) 367-8387 Ext. 133	Contact: Kathy DeSignore (217) 367-8387 Ext. 133

(3) INSTALLATION OF TANKS:

- (a) Number and size of tanks being installed: One compartment tank consisting of: (TK # 3, 4) 5,000 gallons
- (b) Type of tanks: (TK # 3, 4) (Installing) Containment Solutions double wall fiberglass
- (c) Type of piping: (TK # 3, 4) (Installing) Ameron Dualoy 3000/LCX double wall fiberglass
- (d) Product to be stored in each tank: (TK # 3) E-85, (TK # 4) Diesel Fuel
- (e) Type of leak detection being used:

Tank: (TK # 3, 4) - Existing automatic tank gauging console to be used and two new probes will be installed, (TK # 3, 4) - (Installing) Veeder Root TLS 350 Plus Interstitial tank sensor

Piping: (TK # 3) - (Installing) FE Petro STP-MLD mechanical line leak detector, (TK # 3, 4) - (Installing) Veeder Root TLS 350 Plus interstitial piping sump sensors at both submersible sumps and at the new dispenser sump, (TK # 4) - (Installing) Veeder Root TLS350 electronic line leak detector

(f) Corrosion Protection being used:

Tank: (TK # 3, 4) - (Installing) Fiberglass **Piping:** (TK # 3, 4) - (Installing) Fiberglass

- (g) Spill containment devices:
- (h) Overfill prevention devices:
- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.
- (5) GENERAL REQUIREMENTS:
- (6) SPECIAL CONTINGENCIES:

(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK</u> :	
	Contact Person: Chuck Hoenig Phone:

Contractor Registration # Exp.

Sincerely,

cc: Storage Tank Safety Specialist - Fire Department -

Office Coordinator -Division File

(Rev. - 1/98)

James J Offey