OFFICE OF THE ILLINOIS STATE FIRE MARSHAL
Division of Technical Services
1035 Stevenson Drive
Springfield, Illinois 62703-4259
(217)524-7605

Amended

FOR OFFICE USE ONLY
Facility # 2-027658
Permit # 01276-2007INS
Request Rec'd 08/13/2007
Amended Date 09/14/2007
Approval Date 8/20/2007 DS
Permit Expires 2/20/2008

Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Part 170. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE**.

(1) OWNER OF TANKS - Corporation, partnership, or other business entity:	**(2) FACILITY** - name and address where tanks are located:
Unisys Corp 1905 Lunt Elk Grove, IL 60007	Unisys Corp 1905 Lunt Elk Grove, Cook Co., IL
Contact:	Contact: Sauer Gerald R (312) 593-4530

(3) INSTALLATION OF TANKS:

(a) Number and size of tanks being installed: (TK # 4, 5, 6, 7) - 25,000 gallons

(b) Type of tanks: (TK # 4, 5, 6, 7) - (Installing) XERXES double wall fiberglass

(c) Type of piping: (TK # 4, 5, 6, 7) - (Installing) Ameron Dualoy 3000/LCX double wall fiberglass

(d) Product to be stored in each tank: (TK # 4, 5, 6, 7) - Diesel Fuel

(e) Type of leak detection being used:

Tank: **(TK # 4, 5, 6, 7) - (Installing) OPW EECO 2000 interstitial tank sensor, (TK # 4, 5, 6, 7) - (Installing) OPW EECO2000 automatic tank gauge console and probes for inventory purposes only.**

Piping: (TK # 4, 5, 6, 7) - (Installing) American Suction, **(TK # 4, 5, 6, 7) - (Installing) OPW EECO 2000 Interstitial piping sump sensors at tank sumps only.**

(f) Corrosion Protection being used:

Tank: (TK # 4, 5, 6, 7) - (Installing) Fiberglass

Piping: (TK # 4, 5, 6, 7) - (Installing) Fiberglass

(g) Spill containment devices:

(h) Overfill prevention devices:

(4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at www.state.il.us/osfm or by calling (217)785-1020.

(5) GENERAL REQUIREMENTS:

(6) SPECIAL CONTINGENCIES:

(7) PERSON, FIRM OR COMPANY PERFORMING WORK:

Contact Person:
Phone:

Contractor Registration # Exp.

Sincerely,

James J. Coffey

cc: Storage Tank Safety Specialist -
Fire Department -
Office Coordinator -
Division File
(Rev. - 1/98)