



OFFICE OF THE ILLINOIS STATE FIRE MARSHAL  
Division of Petroleum and Chemical Safety  
1035 Stevenson Drive  
Springfield, Illinois 62703-4259  
(217)785-1020

FOR OFFICE USE ONLY  
Facility # 3-045242  
Permit # 01196-2012INS  
Request Rec'd 11/13/2012  
Amended Date  
Approval Date 11/13/2012 JC  
Permit Expires 5/13/2013

**Permit for INSTALLATION of Underground Storage Tank(s) and Piping for Petroleum and Hazardous Substances.**

Permission to install underground storage tank(s) or piping is hereby granted. Such installation must be in complete accordance with acceptable materials as specified in the Federal Register, Part II Environmental Protection Agency, 40 CFR Parts 280 and 281, and also with all sections of 41 Illinois Administrative Code, Parts 174, 175 and 176. The contractor the permit was issued to or an employee of that contractor (this does not include a subcontractor) shall submit a required job schedule for installation of underground storage tank(s) to the Office of the State Fire Marshal, Division of Petroleum and Chemical Safety. **THIS PERMIT IS VALID FOR SIX MONTHS FROM THE APPROVAL DATE.**

<b>(1) OWNER OF TANKS</b> - Corporation, partnership, or other business entity:  The Kroger Company 7770 S. Cicero Avenue Burbank, IL 60459  Contact: Jamie Diercks (708) 499-7997	<b>(2) FACILITY</b> - name and address where tanks are located:  Kroeger Fuel Center #J647 1001 W. Jackson St. Morton, Tazewell Co., IL  Contact: Jamie Diercks (708) 499-7997
--	--

**(3) INSTALLATION OF TANKS:**

- (a) **Number and size of tanks being installed:** One compartment tank consisting of the two following: (TK # 1) - 8,000 gallons, (TK # 2) - 10,000 gallons, and one separate tank consisting of: (TK # 3) - 20,000 gallons
- (b) **Type of tanks:** (TK # 1, 2, 3) - (Installing) Fiberglass Brine Filled Double Wall XERXES
- (c) **Type of piping:** (TK # 1, 2, 3) - (Installing) Chase Secondary Containment OPW AXP - 4" secondary chase piping, (TK # 1, 2, 3) - (Installing) Flexible Double Wall OPW Flexworks CP-15 non corrosive product piping.
- (d) **Product to be stored in each tank:** (TK # 1, 3) - Gasoline, (TK # 2) - Diesel Fuel
- (e) **Type of leak detection being used:**  
**Tank:** (TK # 1, 2, 3) - (Installing) Automatic Tank Gauging Veeder Root TLS 450 for inventory purposes only , (TK # 1, 2, 3) - (Installing) Hydrostatic Reservoir Sensors Interstitial Monitoring Veeder Root TLS 450 Dual Stage for tank leak detection.  
  
**Piping:** (TK # 1, 2, 3) - (Installing) Piping Sump Sensors Interstitial Monitoring Veeder Root TLS 450 at all submersible sumps and at all dispenser sumps , (TK # 1, 2, 3) - (Installing) Electronic Pressurized Line Leak Detection Veeder Root TLS 450
- (f) **Corrosion Protection being used:**  
**Tank:** (TK # 1, 2, 3) - (Installing) Fiberglass Non-Corrosive  
**Piping:** (TK # 1, 2, 3) - (Installing) Flexible Non-Corrosive , (TK # 1, 2, 3) - (Installing) Fiberglass Non-Corrosive
- (g) **Spill containment devices, piping and dispenser containment devices:** (TK # 1, 2, 3) - (Installing) Manhole Pre-manufactured OPW 1C-2100C-EVR
- (h) **Overfill prevention devices:**

- (4) The owner must notify this Office when completion of tank installation has occurred, on the Notification for Underground Storage Tank Form and the licensed contractor must submit the required job schedule for installation to the OSFM prior to the work being performed. Both forms can be obtained at [www.sfm.illinois.gov](http://www.sfm.illinois.gov) or by calling (217)785-1020.

- (5) **GENERAL REQUIREMENTS:** There shall be a minimum of two manufactured slotted or perforated observation wells of at least 4 inches in diameter, installed in each new tank field of tanks larger than 1000 gallons and one well for tanks less than 1000 gallons. A water tight containment shall be installed under all dispensers and at submersible pumps. A hydrostatic test must be performed on all containments. All steel piping for vents, risers, and fills in contact with the ground, backfill, or water shall be dielectrically wrapped or coated. A positive shut off valve shall be installed on pressurized product lines, at the submersibles, or installed at the tank for all suction piping systems. Vent piping is required to be tested from tank to grade level. All steel flex connectors in contact with ground, backfill or water shall have corrosion protection.

**(6) SPECIAL CONTINGENCIES:**

<b>(7) <u>PERSON, FIRM OR COMPANY PERFORMING WORK:</u></b>          Contact Person: Chris Epkins Phone: (309) 347-1819  Contractor Registration # IL-1293 Exp.
---

Sincerely,

*James J. Coffey*

cc: Storage Tank Safety Specialist -  
Fire Department -  
Office Coordinator -  
Division File  
(Rev. - 9/10)